TOWN OF BENNETT

Related Projects: P. E. UNDER PROJECT:

INDEX OF SHEETS

STANDARDS PLANS LIST

SURVEY TABULATION SHEET

SURVEY CONTROL DIAGRAM

ALIGNMENT CONTROL PLAN

ROADWAY PLAN & PROFILE

STORM DRAIN PLAN & PROFILE

SUMMARY OF APPROXIMATE QUANTITIES

TITLE SHEET

TYPICAL SECTION

GENERAL NOTES

TABULATIONS

REMOVAL PLANS

INTERSECTION PLAN PAVING PLAN

TRAFFIC SIGNAL PLANS

Project Number Project Code:

XX


R.O.W. Projects: R.O.W. Project Description

HIGHWAY CONSTRUCTION BID PLANS OF PROPOSED FEDERAL AID PROJECT NO. STU 0704-248

I-70 (EXIT 304) / SH 79 INTERCHANGE IMPROVEMENTS **ARAPAHOE COUNTY**

CONSTRUCTION PROJECT CODE NO. 23180

TABULATION OF LENGTH	& DESIGN	DATA
		ET
STATION	ROAL	WAY
	I-70 EB RAMPS	SH 79
I-70 EB RAMPS		
BEGIN PROJECT		
STA. 10+00.00	3 735	
END PROJECT	1,715	
STA. 53+00.00		
<u>sh 79</u>		
BEGIN PROJECT		
STA. 100+00.00		
END PROJECT		661
STA. 106+60.80		
2 200.00.00		
TOTAL	1,715	661
SUMMARY OF PROJECT LENGTH	FEET	MILES
PROJECT GROSS LENGTH (MILES)	2,376	0.450
DESIGN DATA	I-70 EB RAMPS	SH 79
MAXIMUM RADIUS OF CURVE	1,950'	N/A
MAXIMUM GRADE	3.4%	3.4%
MINIMUM S.S.D. HORIZONTAL	360'	360'
ritingfor b.b.b. nonthoning	300	300
MINIMUM S.S.D. VERTICAL	360'	360'
MAXIMUM DESIGN SPEED	45 MPH*	45 MPH
2040 DESIGN TRAFFIC	DHV=11%	DHV=11%
	ADT=5,600	ADT=11,520
DIN MBILON 2	<u>'</u>	
DHV TRUCK %	15.0%	8.8%
CLEAR ZONE DISTANCE (TANGENT)	24'	24'
CLEAR ZONE DISTANCE (RADIUS)	24'	24'
CONSTRUCTION CLEAR ZONE (MIN 18')	18'	18'



PROJECT LOCATION MAP

AD PLANS

Print Date: 3/29/22 Sheet Revisions File Name: I70-SH79_TITLE SHEET.DWG Date: Comments Init. Horiz. Scale: 0.5:1 Vert. Scale: As Noted Unit Information Unit Leader Initials Short Elliott Hendrickson Inc Colorado Center Tower One Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801 SEH



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

As Constructed		Contract Information	Project No./Code	
	710 0011011 00100	Contractor:		
	l.,	odnitiactor.	0711 0704 040	
	No Revisions:	Resident Engineer:	STU 0704-248	
	Revised:	Project Engineer:	23180	
11011000.		PROJECT STARTED: / / ACCEPTED: / /		
		TROULD STANTED// ACCEPTED//	Sheet Number 1	
	Void:	Comments:		

 \star 45 MPH AT C2, 30 MPH AT C3, 20 MPH AT L3, 30 MPH AT L4

27 INTERCONNECT PLAN 28-30 SIGNING AND STRIPING PLANS 31 DETOUR PLAN

SHEET NO.

2

3

5

6-7

8-11

12-13

14

15

16-18

19

20

21

22-26

32-37 STORMWATER MANAGEMENT PLANS 38-39 EROSION CONTROL PLANS UTILITY GENERAL NOTES 40

41 UTILITY PLAN

42-44 SUBSURFACE UTILITY ENGINEERING (SUE) PLANS

XS1-XS4 ROADWAY CROSS SECTIONS

PLAN	M STANDARD	PAGE
<u>NUMBER</u>	<u>TITLE</u>	<u>NUMBER</u>
■ M-100-1	STANDARD SYMBOLS (3 SHEETS)	
■ M-100-2	ACRONYMS AND ABBREVIATIONS (4 SHEETS)	
☐ M-203-1	APPROACH ROADS	
□ M-203-2	DITCH TYPES	
□ M-203-11	SUPERELEVATION CROWNED AND	
M-203-12	SUPERELEVATION STREETS (2 SHEETS)	
□ M-206-1	EXCAVATION AND BACKFILL FOR STRUCTURES(2 SHEETS)	
□ M-206-2	EXCAVATION AND BACKFILL FOR BRIDGES (2 SHEETS)	17–18
■ M-208-1	TEMPORARY EROSION CONTROL (11 SHEETS)	
☐ M-210-1	MAILBOX SUPPORTS (2 SHEETS)	
☐ M-214-1	NURSERY STOCK DETAILS	
■ M-216-1	SOIL RETENTION COVERING (2 SHEETS)	
■ M-412-1	CONCRETE PAVEMENT JOINTS (9 SHEETS)	.35–39
□ M-412-2	CONCRETE PAVEMENT CRACK REPAIR (4 SHEETS) (NEW, ISSUED ON OCTOBER 7, 2019)	
□ M-510-1	STRUCTURAL PLATE PIPE H-20 LOADING	40
□ M-601-1	SINGLE CONCRETE BOX CULVERT (CAST-IN-PLACE) . (2 SHEETS)	41-42
□ M-601-2	DOUBLE CONCRETE BOX CULVERT (CAST-IN-PLACE) . (2 SHEETS)	43–44
□ M-601-3	TRIPLE CONCRETE BOX CULVERT (CAST-IN-PLACE) . (2 SHEETS)	45-46
	HEADWALL FOR PIPES	47
□ M-601-11	TYPE "S" SADDLE HEADWALLS FOR PIPE	48
□ M-601-12	HEADWALLS AND PIPE OUTLET PAVING	49
□ M-601-20	WINGWALLS FOR PIPE OR BOX CULVERTS (2 SHEETS)	50-51
■ M-603-1	METAL PIPE (4 SHEETS)	52-55
	REINFORCED CONCRETE PIPE	56
□ M-603-3	PRECAST CONCRETE BOX CULVERT	 57
□ M-603-4	CORRUGATED POLYETHYLENE PIPE (AASHTO M294) AN CORRUGATED POLYPROPYLENE PIPE (AASHTO M330) ((REVISED ON MARCH 7, 2022)	
□ M-603-5	POLYVINYL CHLORIDE (PVC) PIPE (AASHTO M304)	59
□ M-603-6	STEEL REINFORCED POLYETHYLENE	60
□ M-603-10	CONCRETE AND METAL END SECTIONS	61
□ M-603-12	TRAVERSABLE END SECTIONS AND SAFETY GRATES . (3 SHEETS)	62–64
	INLET, TYPE C	65
■ M-604-11	INLET, TYPE D	66
□ M-604-12	CURB INLET TYPE R (2 SHEETS)	67-68
	CONCRETE INLET TYPE 13	69
□ M-604-20	MANHOLES (3 SHEETS)	70-72
□ M-604-25	VANE GRATE INLET (5 SHEETS)	73–77
□ M-605-1	SUBSURFACE DRAINS	78

PLAN	M STANDARD PAGE
NUMBER	TITLE NUMBER
■ M-606-1	MIDWEST GUARDRAIL SYSTEM TYPE 3 W-BEAM
□ M-606-13	GUARDRAIL TYPE 7 F-SHAPE BARRIER (4 SHEETS)98-101
□ M-606-14	PRECAST TYPE 7 CONCRETE BARRIER (4 SHEETS) 102-104 (REVISED ON AUGUST 21, 2020)
□ M-606-15	GUARDRAIL TYPE 9 SINGLE SLOPE BARRIER
	WIRE FENCES AND GATES (3 SHEETS)116-118
□ M-607-2	CHAIN LINK FENCE (3 SHEETS)119-121
□ M-607-3	BARRIER FENCE122
□ M-607-4	DEER FENCE, GATES, AND GAME RAMPS (7 SHEETS) 123-127 (REVISED ON JULY 13, 2020)
	PICKET SNOW FENCE128
■ M-607-15	ROAD CLOSURE GATE (9 SHEETS)129-137
	CURB RAMPS (10 SHEETS)138-147
	CURBS, GUTTERS, AND SIDEWALKS (4 SHEETS)148-151
	CATTLE GUARD (2 SHEETS)
	DEER GUARD (2 SHEETS)
□ M-614-1	RUMBLE STRIPS (3 SHEETS)
	SAND BARREL ARRAYS (2 SHEETS)159-160
□ M-615-1	EMBANKMENT PROTECTOR TYPE 3161
□ M-615-2	EMBANKMENT PROTECTOR TYPE 5162
□ M-616-1	INVERTED SIPHON163
□ M-620-1	FIELD LABORATORY CLASS 1
■ M-620-2	FIELD LABORATORY CLASS 2 (2 SHEETS)
□ M-620-11	FIELD OFFICE CLASS 1
■ M-620-12	FIELD OFFICE CLASS 2
□ M-629-1	SURVEY MONUMENTS (2 SHEETS)

COLORADO
DEPARTMENT OF TRANSPORTATION

M&S STANDARDS PLANS LIST

July 31, 2019

Revised on March 7, 2022

ALL OF THE M&S STANDARD PLANS, AS SUPPLEMENTED AND REVISED, APPLY TO THIS PROJECT WHEN USED BY DESIGNATED PAY ITEM OR SUBSIDIARY ITEM.


THE M&S STANDARD PLANS USED TO DESIGN THIS PROJECT ARE INDICATED BY A MARKED BOX **—**, AND WILL BE ATTACHED TO THE PLANS. ALL THE OTHER M&S STANDARD PLANS ARE STILL ELIGIBLE FOR CONSTRUCTION IF APPROVED BY AN APPROPRIATE CDOT ENGINEER.

PLAN	S STANDARD	PAGE
NUMBER		NUMBER
■ S-612-1	DELINEATOR INSTALLATIONS (8 SHEETS)	
□ S-613-1	ROADWAY LIGHTING (6 SHEETS)	179–186
□ S-613-2	ALTERNATIVE ROADWAY LIGHTING (4 SHEETS) (NEW, ISSUED ON SEPTEMBER 30, 2020)	
■ S-614-1	GROUND SIGN PLACEMENT (2 SHEETS)	187-188
■ S-614-2	CLASS SIGNS	189
■ S-614-3	CLASS II SIGNS	190
☐ S-614-4	CLASS III SIGNS (3 SHEETS)	191-193
□ S-614-5	BREAK-AWAY SIGN SUPPORT DETAILSFOR CLASS III SIGNS (2 SHEETS)	
☐ S-614-6	CONCRETE FOOTINGS AND SIGN ISLANDSFOR CLASS III SIGNS (2 SHEETS)	196–197
■ S-614-8	TUBULAR STEEL SIGN SUPPORT DETAILS (7 SHEETS) (REVISED ON DECEMBER 31, 2020)	198-204
S 614 9	PEDESTRIAN PUSH BUTTON POST ASSEMBLY (2 SHEETS) (SUPERSEDED ON JANUARY 23, 2020 BY S-614-45)	.205 206
☐ S-614-10	MARKER ASSEMBLY INSTALLATIONS	207
☐ S-614-11	MILEPOST SIGN DETAIL FOR HIGH SNOW AREAS	208
☐ S-614-12	STRUCTURE NUMBER INSTALLATION (2 SHEETS)	209-210
☐ S-614-14	FLASHING BEACON AND SIGN INSTALLATIONS (4 SHEETS)	211-214
■ S-614-20	TYPICAL POLE MOUNT SIGN INSTALLATIONS	215
□ S-614-21	CONCRETE BARRIER SIGN POST INSTALLATIONS	216-217
■ S-614-22	TYPICAL MULTI-SIGN INSTALLATIONS	
□ S-614-40	TYPICAL TRAFFIC SIGNAL 30'-75' DOUBLE MAST ARMS 65'-75' SINGLE MAST ARMS (5 SHEETS)	
■ S-614-40A	ALTERNATIVE TRAFFIC SIGNAL 25'-55' SINGLE MAST ARMS (4 SHEETS)	
☐ S-614-41	TEMPORARY SPAN WIRE SIGNALS (13 SHEETS)	
■ S-614-42	CABINET FOUNDATION DETAIL (4 SHEETS)	241-244
■ S-614-43	TRAFFIC LOOP AND MISCELLANEOUS SIGNAL DETAILS (8 SHEETS)	
☐ S-614-44	PEDESTAL POLE SIGNALS (2 SHEETS)	253-254
□ S-614-45	PEDESTRIAN PUSH BUTTON POST ASSEMBLY DETAILS (6 (REVISED ON DECEMBER 3, 2020)	SHEETS)
☐ S-614-50	STATIC SIGN MONOTUBE STRUCTURES (12 SHEETS)	
☐ S-614-60	DYNAMIC SIGN MONOTUBE STRUCTURES (14 SHEETS)	
■ S-627-1	PAVEMENT MARKINGS (9 SHEETS)	281-289
■ S-630-1	TRAFFIC CONTROLS FOR HIGHWAY CONSTRUCTION (24 SHEETS)	290-313
■ S-630-2	BARRICADES, DRUMS, CONCRETE BARRIERS (TEMP) AND VERTICAL PANELS	
□ S-630-3	FLASHING BEACON (PORTABLE) DETAILS	
□ S-630-4	STEEL SIGN SUPPORT (TEMPORARY) INSTALLATION DETAILS (2 SHEETS)	
□ S-630-5	PORTABLE RUMBLE STRIPS (TEMPORARY) (2 SHEETS)	
□ S-630-6	EMERGENCY PULL-OFF AREA (TEMPORARY)	320
□ S-630-7	ROLLING ROADBLOCKS FOR TRAFFIC CONTROL	321–323

Print Date: 3/29/22		Sheet Revisions		Sheet Revisions	
File Name: I70-SH79_STAN	NDARD PLAN LIST.DWG		Date:	Comments	
Horiz. Scale: 0.5:1	Vert. Scale: As Noted				
Unit Information	Unit Leader Initials				
Short Elliott Hendrickson Inc Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966				
2000 South Colorado Boulevard	Fax (720) 540-6801				




As Constructed	Project No.		Project No./Code
No Revisions:	STANDARDS	STU 0704-248	
Revised:	Designer: A. MARQUEZ		23180
	Detailer: M. WAGNER	Numbers	
Void:	Sheet Subset: SPL	Subset Sheets: 1 of 1	Sheet Number 2




I-70 RAMP TYPICAL SECTION OFF-RAMP STA 18+35.68 TO STA 23+99.98 ON-RAMP STA 50+14.18 TO STA 51+68.88


*SUBGRADE IS MOISTURE CONDITIONED AND RECOMPACTED (A-6 OR BETTER WITH MIN. R-VALUE OF 19).



SH 79 TYPICAL SECTION STA 102+74.67 TO STA 103+59.21




SH 79 TYPICAL SECTION STA 104+25.10 TO STA 105+30.36




TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125


Project No./Code As Constructed TYPICAL SECTION No Revisions: STU 0704-248 A. MARQUEZ Structure Designer: Revised: 23180 K. KULESZA Numbers Detailer: 3 Void: Sheet Number Sheet Subset: TYPSECT Subset Sheets: 1 of 1



HMA PAVEMENT SECTION (REQUIRES 3 LIFTS)



ASPHALT TO CONCRETE TRANSITION (NOT TO SCALE)




CONCRETE AND HOT MIX ASPHALT SAFETY EDGE DETAIL

P.G.L.	~ Profile Grade Line
H.M.A.	~ Hot Mix Asphalt
H.P.	~ Hinge Point
P.O.S.S.	~ Point of Slope Selection
4	~ Minimum 6" Topsoil or Specified Alternative

Print Date: 3/29/22	
File Name: I70-SH79_TYPICAL	SECTION.DWG
Horiz. Scale: 0.5:1	Vert. Scale: As Noted
Unit Information	Unit Leader Initials

Short Elliott Hendrickson Inc Colorado Center Tower One 么 SEH

Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801



Sheet Revisions

welcome neighbors.

FAX (303) 644-4125

Void:

HMA - Hot Mix Asphalt (Section 403)

Concrete (Section 412)

Special Interval

Pavement Marking (Section 627)

___ Striping (Temp)

K. KULESZA

Numbers

Sheet Subset: SURVTAB | Subset Sheets: 1 of 1

Proiect No./Code

STU 0704-248

23180

Sheet Number

Striping

Short Elliott Hendrickson Inc


Suite 6000 2000 South Colorado Boulevard

Tele. (720) 540-6800

么 SH

TO ESTABLISH GEOMETRIC CONTROL FOR THE CONSTRUCTION OF THIS

PROJECT. THE DEPARTMENT HAS PROVIDED THE FOLLOWING INFORMATION:



X:\AE\B\BENNT\158279\Bennett Interchange Design\Design\Drawings\\70-SH79_Survey Control.dwg 5/3/2021 8:17 AM kku

GENERAL NOTES:

- 1. ALL MATERIAL, EQUIPMENT, INSTALLATION AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, CDOT STANDARD PLANS (M&S STANDARDS), FHWA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) FOR STREETS AND HIGHWAYS AND THE COLORADO SUPPLEMENT THERETO, TOWN OF BENNETT ROADWAY DESIGN AND CONSTRUCTION STANDARDS, TOWN OF BENNETT STORM DRAINAGE CRITERIA MANUAL, TOWN OF BENNETT SANITARY SEWER/WATER SYSTEM DESIGN AND CONSTRUCTION STANDARDS, AND IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS INCLUDED HEREIN.
- 2. FOR PRELIMINARY PLAN QUANTITIES OF PAVEMENT MATERIALS, THE FOLLOWING RATES OF APPLICATION WERE USED.

TACK COAT DILUTED EMULSIFIED
HOT MIX ASPHALT
AGGREGATE BASE COURSE

0.10 GAL. PER SQ. YD. (DILUTED) ASPHALT (SLOW-SETTING)
146.7 LBS. / CU. FT.
133 LBS. / CU. FT.

- 3. DILUTED EMULSIFIED ASPHALT FOR TACK COAT SHALL CONSIST OF 1 PART EMULSIFIED ASPHALT AND 1 PART WATER. THIS WILL NOT BE PAID FOR SEPARATELY AND IS INCLUDED IN THE COST FOR ITEM 403, HOT MIX ASPHALT.
- 4. THE FOLLOWING SHALL BE FURNISHED WITH EACH ASPHALT PAVER.
 - * A SKI TYPE DEVICE AT LEAST 30 FEET IN LENGTH. (50 FEET IN LENGTH FOR FINAL LIFT)
 - * SHORT SKI SHOF
 - * 1500 FEET OF CONTROL LINE AND STAKES
- 5. ANY LAYER OF ASPHALT PAVEMENT THAT IS TO HAVE A SUCCEEDING LAYER PLACED THEREON SHALL BE COMPLETED FULL WIDTH BEFORE THE SUCCEEDING LAYER IS PLACED.
- 6. A TACK COAT IS REQUIRED BETWEEN ALL LIFTS OF HMA, WHICH WILL BE CONSIDERED SUBSIDIARY TO ITEM 403 AND WILL NOT BE PAID FOR SEPARATELY.
- 7. WHERE PAVEMENT IS TO ABUT EXISTING PAVEMENT, THE EXISTING PAVEMENT SHALL BE REMOVED TO A NEAT VERTICAL LINE, USING A SAW OR OTHER METHOD AS APPROVED, TO CREATE A CLEAN CONSTRUCTION JOINT. THERE SHALL BE NO SEPARATE PAYMENT FOR SAW CUTTING. THE CONTRACTOR WILL ALSO BE REQUIRED TO PAINT THE EDGE WITH DILUTED EMULSIFIED ASPHALT (SLOW—SETTING) PRIOR TO PAVING OPERATIONS. THE RATE OF APPLICATION SHALL BE AS DETERMINED BY THE ENGINEER AT THE TIME OF APPLICATION.
- 8. WATER SHALL BE USED AS A DUST PALLIATIVE AS DIRECTED BY THE ENGINEER. LOCATIONS SHALL BE AS DIRECTED. COST FOR DUST PALLIATIVE SHALL NOT BE MEASURED AND PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE WORK.
- 9. DEPTH OF MOISTURE DENSITY CONTROL FOR THIS PROJECT SHALL BE AS FOLLOWS:

FULL DEPTH OF EMBANKMENT FOR ROADWAY SUBGRADE BELOW ROADBED ~ 2 FEET DEPTH BASES OF CUTS ~ 8 INCHES DEPTH BASES OF FILLS ~ 8 INCHES DEPTH (AFTER TOPSOIL STRIPPING)

- 10. EXCAVATION REQUIRED FOR COMPACTION OF BASES OF CUT AND FILLS WILL BE CONSIDERED SUBSIDIARY TO ITEM 203, AND WILL NOT BE PAID FOR SEPARATELY.
- 11. THE TYPE OF COMPACTION FOR THIS PROJECT WILL BE AASHTO T-180, AND T-99 FOR EMBANKMENT.
- 12. FULL COMPLIANCE PAVEMENT MARKINGS AND ROADSIDE DELINEATION SHALL BE IN PLACE AT THE END OF EACH WORKING DAY UNLESS OTHERWISE APPROVED BY THE ENGINEER.
- 13. IF ANY SOIL CONTAMINATION IS SUSPECTED WHILE EXCAVATING, IMMEDIATELY CONTACT THE ENGINEER AND FOLLOW STANDARD SPECIAL 250.
- 14. THE CONTRACTOR SHALL NOT STOCKPILE ANY MATERIAL WITHIN CDOT R.O.W. UNLESS APPROVED BY THE ENGINEER.
- 15. THE CONTRACTOR SHALL SUBMIT A PLAN ADDRESSING LOCAL DRAINAGE DURING EACH PHASE OF CONSTRUCTION TO THE ENGINEER FOR REVIEW. THIS SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE WORK.
- 16. CONTROL OF SURFACE RUNOFF AND REPAIR OF DAMAGES RESULTING FROM RUNOFF IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE INCLUDED IN THE COST OF THE WORK.
- 17. ALL SHOULDERS AND OTHER PAVED AREAS SHALL BE SWEPT ON A DAILY BASIS TO REMOVE ANY FOREIGN DEBRIS FROM THE SHOULDER AND TRAVELED WAY. ALL SWEEPING OPERATIONS SHALL BE DONE BY A PICK-UP TYPE BROOM AND SHALL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE WORK.
- 18. THE CONTRACTOR SHALL PROTECT ALL EXISTING UTILITIES DURING CONSTRUCTION AND IS RESPONSIBLE FOR ANY DAMAGE THERETO.
- 19. CLEARING AND GRUBBING WILL NOT BE ALLOWED BEYOND THE CONSTRUCTION LIMITS OR REQUIRED CLEAR ZONE. THIS WORK WILL BE MEASURED AND PAID FOR PER ACRE.
- 20. APPROPRIATE MEASURES WILL BE TAKEN TO PREVENT THE INTRODUCTION AND SPREAD OF NOXIOUS WEEDS BY RE-ESTABLISHING A PERMANENT DESIRABLE VEGETATION COMMUNITY WITHIN PROJECT LIMITS, WHICH THE CONSTRUCTION CONTRACTOR MUST FOLLOW.

Print Date: 3/29/22		Sheet Revisions			Ī	
File Name: I70—SH79_GEN	NERAL NOTES.DWG		Date:	Comments	Init.	
Horiz. Scale: 0.5:1	Vert. Scale: As Noted					
Unit Information	Unit Leader Initials					ĺ
Short Elliott Hendrickson Ind Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966					
2000 South Colorado Boulevard	Fax (720) 540-6801					



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125 As Constructed

No Revisions:

Revised:

Designer: A. MARQUEZ Structure Numbers

Void:

Project No./Code

STU 0704-248

23180

Sheet Subset: GENNOTES Subset Sheets: 1 of 2 Sheet Number 6

- 21. IT IS ESTIMATED THAT 8 HOURS OF WILDLIFE BIOLOGIST WILL BE REQUIRED FOR THIS PROJECT.
- 22. HAZARDOUS MATERIALS, INCLUDING FUELS AND LUBRICATING OILS, SHALL NOT BE STORED ANYWHERE ON THE CORRIDOR.
- 23. THE CONTRACTOR SHALL LIMIT CONSTRUCTION ACTIVITIES TO THOSE AREAS WITHIN THE LIMITS OF DISTURBANCE AND/OR TOES OF SLOPE AS SHOWN ON THE PLANS AND CROSS SECTIONS. ANY DISTURBANCE BEYOND THESE LIMITS SHALL BE RESTORED TO ORIGINAL CONDITIONS BY THE CONTRACTOR AT HIS/HER OWN EXPENSE. CONSTRUCTION ACTIVITIES, IN ADDITION TO NORMAL CONSTRUCTION PROCEDURES, SHALL INCLUDE THE PARKING OF VEHICLES OR EQUIPMENT, DISPOSAL OF LITTER, AND ANY OTHER ACTION WHICH WOULD ALTER EXISTING CONDITIONS.
- 24. IN FILL SECTIONS, THE BASES UPON WHICH EMBANKMENT MATERIAL IS TO BE PLACED BELOW THE ROADBED SHALL BE SCARIFIED TO A DEPTH OF 8 INCHES AND THEN RECOMPACTED WITH MOISTURE AND DENSITY CONTROL. IN CUT SECTIONS, THE EARTH SHALL BE REMOVED FROM THE FULL WIDTH OF THE ROADBED TO THE DESIGNATED DEPTH AND THE EARTH SUBGRADE SHALL BE THOROUGHLY SCARIFIED TO A DEPTH OF 2 FEET AND THEN RECOMPACTED WITH MOISTURE AND DENSITY CONTROL. THE MOISTURE CONTENT OF THE SCARIFIED MATERIAL SHALL BE INCREASED OR DECREASED, AS NECESSARY, TO OBTAIN THE TYPE OF COMPACTION SPECIFIED. SCARIFICATION AND COMPACTION WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED SUBSIDIARY TO ROADWAY CONTRACT PAY ITEM 203, UNCLASSIFIED EXCAVATION (CIP)
- 25. ALL EMBANKMENT MATERIAL SHALL CONSIST OF MATERIAL WHICH IS A NON-EXPANSIVE, GRANULAR SOIL. THE CONTRACTOR SHALL FURNISH EVIDENCE THAT THE EMBANKMENT MATERIAL FROM THE SITE OR OTHER SOURCES, FOR USE IN THE ROADWAY EMBANKMENT, MEETS THE REQUIREMENTS AND SHALL PAY FOR SUCH TESTS AS MAY BE REQUIRED TO SHOW COMPLIANCE. NEW EMBANKMENT SHALL BE BENCHED INTO THE EXISTING SLOPES WHERE REQUIRED IN ACCORDANCE WITH 203.06 OF THE STANDARD SPECIFICATIONS. THE MINIMUM THICKNESS OF THE TOPSOIL SHALL BE 6 INCHES AND WILL BE OBTAINED FROM THE CONTRACTOR'S SOURCES. THE TOPSOIL SHALL BE APPLIED TO ALL DISTURBED AREAS, OR AS DIRECTED BY THE ENGINEER.
- 26. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL EXISTING PROPERTY ACCESSES (INCLUDING RESIDENTIAL AND COMMERCIAL) AT ALL TIMES DURING CONSTRUCTION AT NO ADDITIONAL COST TO THE PROJECT.
- 27. THE CONTRACTOR SHALL MASK ALL SIGNS CONFLICTING WITH CONSTRUCTION SIGNING. THE MASKING OF SIGNS WILL NOT BE MEASURED AND PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF THE WORK.
- 28. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FOR ALL APPLICABLE AGENCIES PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- 29. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ASPECTS OF SAFETY INCLUDING, BUT NOT LIMITED TO, EXCAVATION, TRENCHING, SHORING, TRAFFIC CONTROL, AND SECURITY. REFER TO OSHA PUBLICATION 2226, EXCAVATING AND TRENCHING.
- 30. THE CONTRACTOR SHALL HAVE, ON SITE AT ALL TIMES, ONE (1) COPY OF THE APPROVED PLANS, ONE (1) COPY OF THE APPROPRIATE STANDARDS AND SPECIFICATIONS, AND A COPY OF ANY PERMITS AND EXTENSION AGREEMENTS NEEDED FOR THE JOB.
- 31. IF, DURING THE CONSTRUCTION PROCESS, CONDITIONS ARE ENCOUNTERED WHICH COULD INDICATE A SITUATION THAT IS NOT IDENTIFIED IN THE PLANS OR SPECIFICATIONS, THE CONTRACTOR SHALL CONTACT THE ENGINEER IMMEDIATELY.
- 32. A STATE CONSTRUCTION DEWATERING WASTEWATER DISCHARGE PERMIT IS REQUIRED FOR WATER THAT IS DISCHARGED INTO A STREAM, STORM SEWER, CHANNEL, IRRIGATION DITCH, OR ANY WATERS OF THE UNITED STATES.
- 33. THE CONTRACTOR SHALL COMPLY WITH ALL TERMS AND CONDITIONS OF THE COLORADO PERMIT FOR STORMWATER DISCHARGE (CONTACT COLORADO DEPARTMENT OF HEALTH, WATER QUALITY CONTROL DIVISION, (303) 692-3590), THE STORMWATER MANAGEMENT PLAN. AND THE EROSION CONTROL PLAN.
- 34. TEMPORARY EROSION CONTROL DURING CONSTRUCTION SHALL BE PROVIDED AS SHOWN ON THE EROSION CONTROL PLAN, AND AS DIRECTED BY THE ENGINEER. ALL EROSION CONTROL MEASURES SHALL BE MAINTAINED IN GOOD REPAIR BY THE CONTRACTOR, UNTIL SUCH TIME AS THE ENTIRE DISTURBED AREAS IS STABILIZED WITH HARD SURFACE OR LANDSCAPING.
- 35. THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION TRAFFIC CONTROL PLAN, IN ACCORDANCE WITH MUTCD AND CDOT STANDARD FOR TRAFFIC CONTROL S-630-1, TO TOWN FOR APPROVAL, PRIOR TO ANY CONSTRUCTION ACTIVITIES WITHIN, OR AFFECTING, THE RIGHT-OF-WAY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ANY AND ALL TRAFFIC CONTROL DEVICES AS MAY BE REQUIRED BY THE CONSTRUCTION ACTIVITIES.
- 36. THERE SHALL BE NO SITE CONSTRUCTION ACTIVITIES ON SATURDAYS, UNLESS SPECIFICALLY APPROVED BY THE ENGINEER, AND NO SITE CONSTRUCTION ACTIVITIES ON SUNDAYS OR HOLIDAYS, UNLESS THERE IS PRIOR WRITTEN APPROVAL BY CDOT AND THE TOWN. A MINIMUM 48 HOURS NOTICE IS REQUIRED.
- 37. WHERE FENCES ARE IMPACTED BY THE CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING, RESETTING, OR MAINTAINING THE IMPACTED FENCE. ALL PRIVATE LIVESTOCK AREAS SHALL BE MAINTAINED BY THE CONTRACTOR THROUGHOUT CONSTRUCTION OF NEW FENCES OR TEMPORARY FENCES, IF NECESSARY. TEMPORARY FENCE WILL NOT BE MEASURED AND PAID FOR SEPARATELY.
- 38. THE UTILITY INFORMATION SHOWN ON THE PLANS IS PLOTTED FROM THE BEST AVAILABLE INFORMATION. THE CONTRACTOR IS FULLY RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES AND AVOIDING THEM. REFER TO PARAGRAPH 105.11 OF THE STANDARD SPECIFICATIONS. CONDUIT RUNNING LINE ALIGNMENT MAY BE MOVED TO AVOID EXISTING UTILITIES WITH THE APPROVAL OF THE ENGINEER. CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY OF ANY UTILITY CONFLICT WHICH CANNOT BE READILY RESOLVED AND WHICH MAY REQUIRE RE—DESIGN OF ANY PART OF THE PROJECT.

GENERAL NOTES (CON'T.)

- 39. IT IS ESTIMATED THAT 20 HOURS OF POTHOLING WILL BE REQUIRED FOR THE PROJECT, AND WILL BE PAID UNDER ITEM 203, POTHOLING. THE CONTRACTOR SHALL SUBMIT A POTHOLING PLAN TO THE ENGINEER AT THE PRE—CONSTRUCTION CONFERENCE FOR APPROVAL WHICH DESCRIBES A PLAN FOR POTHOLING ALL EXISTING FACILITIES THAT MAY BE IMPACTED BY CONSTRUCTION.
- 40. IT IS ANTICIPATED THAT ONE MOBILIZATION WILL BE REQUIRED FOR THIS PROJECT. ONE (1) LUMP SUM (ITEM 626) WILL BE PAID FOR BY THE PROJECT.
- 41. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE EXISTING CONDITIONS.
- 42. THE CONTRACTOR MUST REVIEW WORK SITES WITH THE ENGINEER TO ENSURE WETLANDS THAT ARE IDENTIFIED SHALL BE PROTECTED WITH TEMPORARY FENCE. TEMPORARY FENCE WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF THE WORK.
- 43. SEVERITY OF POTENTIAL SULFATE EXPOSURE ON THIS PROJECT IS CLASS 3. THE CONTRACTOR, AT HIS OWN EXPENSE, SHALL HAVE A CERTIFIED LABORATORY TEST OF THE SUBGRADE AS PER THE CDOT FIELD MATERIAL MANUAL. TESTING SHALL BE AT THE SAME SCHEDULE AND FREQUENCY AS REQUIRED FOR A PRELIMINARY SOIL SURVEY. THE CONTRACTOR MAY PROPOSE A DIFFERENT CLASS OF EXPOSURE FOR THE PROJECT BASED ON THOSE TEST RESULTS.
- 44. THE CONTRACTOR SHALL COMPLY WITH ARTICLE 1.5 OF TITLE 9, CRS ("EXCAVATION REQUIREMENTS") WHEN EXCAVATING OR GRADING IS PLANNED IN THE AREA OF UNDERGROUND UTILITY FACILITIES. THE CONTRACTOR SHALL NOTIFY ALL AFFECTED UTILITIES AT LEAST TWO (2) BUSINESS DAYS, NOT INCLUDING THE ACTUAL DAY OF NOTICE, PRIOR TO COMMENCING SUCH OPERATIONS. THE CONTRACTOR SHALL CONTACT THE UTILITY NOTIFICATION CENTER OF COLORADO (UNCC) AT 811, TO HAVE LOCATIONS OF UNCC REGISTERED LINES MARKED BY MEMBER COMPANIES. ALL OTHER UNDERGROUND FACILITIES SHALL BE LOCATED BY CONTACTING THE RESPECTIVE OWNER. UTILITY SERVICE LATERALS SHALL ALSO BE LOCATED PRIOR TO BEGINNING EXCAVATION OR GRADING. THE CONTRACTOR SHALL LOCATE NON—MEMBER UTILITIES, SUCH AS STORM SEWER AND DITCH FACILITIES AS NECESSARY TO PREVENT DAMAGE THERETO. THE CONTRACTOR SHALL SUBMIT AN IREA ENERGY BUILDERS CALL LINE APPLICATION FOR EVERY IREA ENERGY WORK ELEMENT THAT IS TO BE COORDINATED WITH THE PROJECT.
- 45. THE CONTRACTOR SHALL PROVIDE ONE FIELD OFFICE (CLASS 2), ONE FIELD LABORATORY (CLASS 2), AND ONE SANITARY FACILITY.
- 46. ALL REMOVED ITEMS BECOME THE PROPERTY OF THE CONTRACTOR TO BE DISPOSED OF OFF-SITE WITH THE EXCEPTION OF ALL SIGNS, DELINEATORS, SIGNALS, AND ITS EQUIPMENT, WHICH ARE THE PROPERTY OF THE TOWN OF BENNETT AND SHALL BE DELIVERED TO THE TOWN UNDAMAGED. THE CONTRACTOR SHALL CONTACT THE TOWN FOR FURTHER COORDINATION.
- 47. THE CONTRACTOR SHALL PROTECT ALL MONUMENTS OUTSIDE OF THE CONSTRUCTION LIMITS FROM DAMAGE.
- 48. SMOOTHNESS CATEFORY FOR THIS PROJECT SHALL BE MRI CATEGORY I.
- 49. THE CONTRACTOR SHALL USE A STRING LINE FOR ALL HMA PAVING.
- 50. THE CONTRACTOR SHALL SUBMIT A PAVING SCHEDULE TO THE ENGINEER AT LEAST 5 WORKING DAYS PRIOR TO THE PRE-PAVING CONFERENCE. PAVING SHALL NOT BEGIN UNTIL THE SCHEDULE HAS BEEN ACCEPTED IN WRITING BY THE FNGINFFR
- 51. THE CONTRACTOR SHALL NOT STOCKPILE MATERIAL OR EQUIPMENT WITHIN 30 FEET OF THE EDGE OF TRAVEL WAY.
- 52. ADDITIONAL MOBILIZATIONS REQUIRED FOR TEMPORARY STRIPING OPERATIONS WILL NOT BE PAID FOR AND ALL TEMPORARY STRIPING WILL BE PAID AT THE UNIT COST REGARDLESS OF ADDITIONAL MOBILIZATIONS.
- 53. CONTRACTOR NOT AUTHORIZED TO PERFORM ANY WORK OUTSIDE RIGHT-OF-WAY.
- 54. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION SURVEYING, BOTH LAYOUT AND STAKING OF ALL IMPROVEMENTS FOR APPROVAL BY THE TOWN PRIOR TO INSTALLATION, AND AS—BUILTS OF FINAL INSTALLATIONS.

 DISCREPANCIES TO THE BASE INFORMATION SHALL BE BROUGHT TO THE TOWN'S ATTENTION FOR A DECISION PRIOR TO COMMENCING WITH THE WORK. NOTIFICATION OF REQUEST FOR FIELD REVIEW SHALL BE MADE A MINIMUM OF 24 HOURS IN ADVANCE. CONSTRUCTION SURVEYING WILL BE PAID FOR UNDER ITEM 625, CONSTRUCTION SURVEYING, ONE (1) LUMP SUM.
- 55. THIS PROJECT IS NOT SUBJECT TO INCENTIVE/DISINCENTIVE PAYMENTS FOR ASPHALT PAVEMENT OR CONCRETE PAVEMENT.
- 55. AGGREGATE BASE COURSE CLASS 6 SHALL BE UNDERLAIN BY TWO FEET OF MINIMUM R-19 MATERIAL.
- 56. RECLAIMED ASPHALT PAVEMENT (RAP), ASPHALT MILLINGS, OR ASPHALT IN ANY FORM WHATSOEVER SHALL NOT BE SUBSTITUTED FOR OR USED IN AGGREGATE BASE COURSE (CLASS 6).
- 57. EARLY OPENING CLASS P CONCRETE SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 3,000 PSI BEFORE BEING OPENED TO TRAFFIC.
- 58. DOWEL BARS AND TIE BARS SHALL BE REQUIRED FOR ALL PCCP IN ACCORDANCE WITH M STANDARD M-412-1. DOWEL BARS AND TIE BARS SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE WORK.
- 59. SEAL JOINTS WITH AN APPROVED SEALING MATERIAL.
- 60. DURING SUSPENSION OF WORK, NO TRAFFIC CONTROL INSPECTION DAYS WILL BE PAID.
- 61. IT IS ESTIMATED THAT 150 DAYS OF PUBLIC INFORMATION MANAGEMENT (TIER IV) WILL BE REQUIRED FOR THIS PROJECT.

	, ,					
Pr	Print Date: 3/29/22			Sheet Revisions		
Fil	e Name: I70-SH79_GENER	AL NOTES.DWG		Date:	Comments	Init.
Н	oriz. Scale: 0.5:1	Vert. Scale: As Noted				
Ur	nit Information	Unit Leader Initials				
1	Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966				
SE		Fax (720) 540-6801				



62. THE CONTRACTOR SHALL COMPLY WITH ALL LOCAL AGENCY(S) NOISE ORDINANCES AND/OR OTHER RESTRICTIONS APPLICABLE TO NIGHTTIME CONSTRUCTION ACTIVITIES FOR PROJECTS WITHIN THE LOCAL MUNICIPAL COVERAGE AREAS. PROJECTS FALLING WITHIN UNINCORPORATED AREAS OF A COUNTY WILL BE GOVERNED BY COUNTY CODE. THE CONTRACTOR SHALL COORDINATE WITH THE LOCAL AGENCY(S) AND/OR CDOT FOR ALL NECESSARY NOISE EXEMPTIONS OR NOTICES, NOISE PERMIT VARIANCES, AND APPROVALS TO DO NIGHT WORK AS REQUIRED. IF LOCAL AGENCY NIGHTTIME NOISE RESTRICTIONS DO NOT EXIST AND THERE ARE NOISE SENSITIVE RECEPTORS IN THE PROJECT AREA, THE APPROVALS TO DO NIGHTTIME WORK SHALL BE APPROVED THROUGH THE CDOT ENGINEER. STANDARD NOISE CONTROLS AND BEST MANAGEMENT PRACTICES FOR REDUCING EQUIPMENT AND CONSTRUCTION ACTIVITY NOISE LEVELS SHALL BE UTILIZED IN ALL CASES AND WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO CONSISTENTLY EMPLOY WHEN WORKING IN NOISE SENSITIVE AREAS AFTER 7:00 P.M. FOR THIS PROJECT, THE CONTRACTOR IS REQUIRED TO REVIEW AND UNDERSTAND ALL LOCAL AGENCY ORDINANCES WITH PROJECT APPLICABLE NIGHT RESTRICTIONS. WHEN CONDITIONS APPLY, THE CONTRACTOR SHALL SUBMIT A NIGHTTIME NOISE ORDINANCE MEMORANDUM(S) TO ALL JURISDICTIONAL LOCAL AUTHORITIES. THIS MEMORANDUM SHALL REQUEST CONSTRUCTION NOISE EXEMPTIONS FOR NIGHT WORK OPERATIONS (AT LEAST TWO WEEKS PRIOR TO THE PROPOSED NIGHT WORK START DATE) WHERE CONSTRUCTION WORK IS SCHEDULED BETWEEN THE HOURS OF 7:00 P.M. AND 7:00 A.M. THE FOLLOWING INFORMATION SHOULD BE INCLUDED IN THE EXEMPTION REQUEST SUBMITTALS AND SENT TO THE CITY/COUNTY ENGINEER: (1) REQUESTING ENTITY, (2) CONTACT PERSON AND PHONE NUMBER, (3) LOCATION OF THE WORK, (4) REASONS NIGHT WORK IS BEING REQUESTED, (5) TYPE OF ACTIVITIES PROPOSED TO OCCUR AT NIGHT, (6) EQUIPMENT PROPOSED TO BE USED AT NIGHT, (7) START AND END DATE PROPOSED, (8) TOTAL NUMBER OF NIGHTS WORK IS PROPOSED TO OCCUR. ALL NIGHTTIME CONSTRUCTION ACTIVITIES SUBJECT TO NOISE LEVEL RESTRICTIONS CANNOT BEGIN UNTIL THE NECESSARY DOCUMENTATION AND NOTIFICATIONS HAVE BEEN APPROVED BY THE LOCAL AGENCY AUTHORITY, THE CDOT ENGINEER AND/OR THE REGION'S NOISE SPECIALIST. ALL EXEMPTION REQUESTS AND PERMITTING REQUIREMENTS WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE WORK.

ENVIRONMENTAL NOTES:

1. TREE TRIMMING/REMOVAL

TREE TRIMMING AND/OR REMOVAL ACTIVITIES SHALL BE COMPLETED BEFORE BIRDS BEGIN TO NEST OR AFTER THE YOUNG HAVE FLEDGED. IN COLORADO, MOST NESTING AND REARING ACTIVITIES OCCUR BETWEEN APRIL 1 AND AUGUST HOWEVER, SINCE SOME BIRDS NEST AS EARLY AS FEBRUARY, A NESTING BIRD SURVEY SHALL BE CONDUCTED BY A BIOLOGIST BEFORE ANY TREE TRIMMING OR REMOVAL ACTIVITIES BEGIN.

2. CLEARING/GRUBBING ACTIVITIES

CLEARING AND GRUBBING OF VEGETATION THAT MAY DISTURB GROUND NESTING BIRDS SHALL BE COMPLETED BEFORE BIRDS BEGIN TO NEST OR AFTER THE YOUNG HAVE FLEDGED. IF WORK ACTIVITIES ARE PLANNED BETWEEN APRIL 1 AND AUGUST 31, VEGETATION SHALL BE REMOVED AND/OR TRIMMED TO A HEIGHT OF SIX (6) INCHES OR LESS PRIOR TO APRIL 1. ONCE VEGETATION HAS BEEN REMOVED AND/OR TRIMMED, APPROPRIATE MEASURES, I.E. REPEATED MOWING/TRIMMING, SHALL BE IMPLEMENTED TO ASSURE VEGETATION DOES NOT GROW MORE THAN SIX (6) INCHES. FAILURE TO MAINTAIN VEGETATION HEIGHT OF SIX (6) INCHES OR LESS MAY POSTPONE PROJECT CONSTRUCTION.

. BIRDS OF PREY:

TOWN OF BENNETT 207 MUEGGE WAY

BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

A NEST SURVEY MUST BE CONDUCTED SEVEN (7) DAYS PRIOR TO CONSTRUCTION. IF ANY RAPTORS/NESTS ARE OBSERVED THEN COLORADO PARKS AND WILDLIFE MUST BE CONTACTED AND THEIR GUIDELINES FOLLOWED.

- 4. IN THE EVENT THAT SUSPECTED ASBESTOS CONTAINING MATERIAL (ACM) IS ENCOUNTERED, INCLUDING WITH BURIED UTILITIES, THE CONTRACTOR WILL FOLLOW CDOT SPECIFICATION 250.07 ASBESTOS—CONTAINING MATERIAL MANAGEMENT, AS WELL AS CDOT REGULATED ASBESTOS—CONTAMINATED SOIL MANAGEMENT STANDARD OPERATING PROCEDURE. ADDITIONALLY, DEPENDING ON THE TYPE OF ACM, THIS MATERIAL MUST ALSO BE ABATED IN ACCORDANCE WITH EITHER SECTION 5.5 OF THE SOLID WASTE REGULATIONS, OR REGULATION NO. 8 OF THE AIR QUALITY CONTROL COMMISSION REGULATIONS.
- 5. ALTHOUGH ENCOUNTERING IMPACTED SOIL OR GROUNDWATER IS NOT EXPECTED, WORKERS SHALL BE ALERT DURING EXCAVATION FOR ANY VISUAL OR OLFACTORY SIGNS OF CONTAMINATION. IF IMPACTED SOIL AND/OR GROUNDWATER IS ENCOUNTERED, WORK WILL STOP IMMEDIATELY AND THE PROCEDURES OUTLINED IN THE COLORADO DEPARTMENT OF TRANSPORTATION (CDOT) SPECIFICATION 250 ENVIRONMENTAL HEALTH AND SAFETY MANAGEMENT SHALL BE FOLLOWED.
- 6. THE CONTRACTOR SHALL CONTROL FUGITIVE DUST THROUGH IMPLEMENTATION OF SECTIONS 107.24, 209, AND 250 OF CDOT'S STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, AND THE AIR POLLUTION CONTROL DIVISION'S AIR POLLUTANT EMISSION NOTIFICATION (APEN) REQUIREMENTS.

THE FOLLOWING BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED DURING CONSTRUCTION:

- MAINTAIN ENGINES AND EXHAUST SYSTEMS ON CONSTRUCTION EQUIPMENT AND VEHICLES IN GOOD WORKING ORDER. PROHIBIT TAMPERING WITH EQUIPMENT TO INCREASE HORSEPOWER OR DISABLING EMISSION CONTROL DEVICES. EQUIPMENT IS SUBJECT TO INSPECTION BY THE PROJECT MANAGER TO ENSURE MAINTENANCE IS CONDUCTED REGULARLY.
- PROHIBIT UNNECESSARY IDLING OF CONSTRUCTION EQUIPMENT AND VEHICLES.
- LOCATE STAGING AREAS AND STATIONARY CONSTRUCTION EQUIPMENT/DIESEL ENGINES AS FAR AS POSSIBLE FROM RESIDENCES AND OTHER SENSITIVE RECEPTORS.
- COVER, WET, COMPACT, OR CHEMICAL STABILIZATION TO CONTROL DUST FROM DISTURBED AREAS AND EXCAVATED MATERIALS DURING CONSTRUCTION. MINIMIZE DISTURBED AREAS, PARTICULARLY DURING DRY WEATHER CONDITIONS, AND USE WIND BARRIERS AS APPROPRIATE.
- EMPLOY WHEEL WASH STATIONS AT POINTS OF INGRESS/EGRESS. USE STREET SWEEPERS TO REMOVE SOIL TRACKED ONTO ADJACENT ROADWAYS.
- 8. IF PALEONTOLOGICAL OR ARCHAEOLOGICAL/CULTURAL RESOURCES ARE UNCOVERED DURING PROJECT CONSTUCTION, WORK IN THE IMMEDIATE AREA OF THE FIND SHALL CEASE, AND EITHER THE CDOT HQ PALEONTOLOGIST (NICOLE PEAVEY: 303.757.9632, NICOLE.PEAVEY@STATE.CO.US) OR THE CDOT HQ ARCHAEOLOGIST (GREG WOLFF: 303.757.9158, GREG.WOLFF@STATE.CO.US) SHALL BE NOTIFIED AS SOON AS POSSIBLE PER SECTION 107.23 OF THE STANDARD SPECIFICATIONS.

As Constructed	GENERAL NOTES Project No./		Project No./Code
No Revisions:	GENERA	STU 0704-248	
Revised:	Designer: A. MARQUEZ	1 -	23180
	Detailer: M. WAGNER	Numbers	_
Void:	Sheet Subset: GENNOTES	Subset Sheets: 2 of 2	Sheet Number 7

INDEX			CONTRACT		UNIT	Roadway		PROJE	ECT TOTALS	
воок	OOK PAGE SHEET		ITEM NO.		UNIT	PLAN	AS CONST.	PLAN	AS CONST	
1			201-00001	Clearing and Grubbing	ACRE	0.64		0.64		
			202-00010	Removal of Tree	EACH	2		2		
			202-00090	Removal of Delineator	EACH	10		10		
			202-00210	Removal of Concrete Pavement	SY	1,644		1,644		
			202-00220	Removal of Asphalt Mat	SY	1,634		1,634		
			202-00700	Removal of Light Standard	EACH	2		2		
			202-00810	Removal of Ground Sign	EACH	5		5		
			202-00821	Removal of Sign Panel	EACH	1		1		
			202-01130	Removal of Guardrail Type 3	LF	330		330		
			202-04002	Clean Culvert	EACH	5		5		
			203-00010	Unclassified Excavation (Complete In Place)	СҮ	2,241		2,241		
			203-01597	Potholing	HOUR	20		20		
			207-00700	Topsoil (Onsite)	СУ	485		485		
			207-00704	Subgrade Soil Preparation	SY	2,909		2,909		
			208-00002	Erosion Log Type 1 (12 Inch)	LF	300		300		
			208-00020	Silt Fence	LF	1,800		1,800		
			208-00046	Pre-fabricated Concrete Washout Structure (Type 1)	EACH	1		1		
			208-00075	Pre-fabricated Vehicle Tracking Pad	EACH	2		2		
			208-00103	Removal and Disposal of Sediment (Labor)	HOUR	8		8		
			208-00105	Removal and Disposal of Sediment (Equipment)	HOUR	8		8		
			208-00106	Sweeping (Sediment Removal)	HOUR	24		24		
			210-00810	Reset Ground Sign	EACH	13		13		
			210-01011	Reset Gate	EACH	1		1		
			210-04020	Modify Inlet	EACH	1		1		
			212-00706	Seeding (Native) Drill	ACRE	1.50		1.50		
			213-00002	Mulching (Weed Free Hay)	ACRE	0.80		0.80		
			213-00061	Mulch Tackifier	LB	162		162		
			216-00201	Soil Retention Blanket (Straw-Coconut) (Biodegradable Class 1)	SY	3,365		3,365		
			217-00020	Herbicide Treatment	HOUR	8		8		
			240-00000	Wildlife Biologist	HOUR	8		8		

Print Date: 3/29/22		
File Name: I70—SH79_SOAQ.D	WG	
Horiz. Scale: 0.5:1	Vert. Scale: As Noted	
Unit Information	Unit Leader Initials	
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966	

	Sheet Revisions							
	Date:	Comments	Init.					
\Box								



As Constructed	SUMMARY OF	Project No./Code			
No Revisions:	QUAN	TITIES	STU 0704-248		
Revised:	Designer: A. MARQUEZ		23180		
	Detailer: M. WAGNER	Numbers	_		
Void:	Sheet Subset: SOAQ	Subset Sheets: 1 of 4	Sheet Number 8		

	INDEX		CONTRACT	CONTRACTITEM	UNIT	Roadway			PROJECT TOTALS	
воок	PAGE	SHEET	ITEM NO.	CONTRACT ITEM	UNIT	PLAN	AS CONST.		PLAN	AS CONST.
			304-06000	Aggregate Base Course (Class 6)	TON	1,097			1,097	
			403-00721	Hot Mix Asphalt (Patching) (Asphalt)	SY	200			200	
	·····		403-33841	Hot Mix Asphalt (Grading S) (100) (PG 64-22)	TON	496			496	-
			403-34871	Hot Mix Asphalt (Grading SX) (100) (PG 76-28)	TON	165			165	
			412-00850	Concrete Pavement (8-1/2 Inch)	SY	2,113			2,113	
	······································		503-00036	Drilled Shaft (36 Inch)	LF	57			57	
			603-01240	24 Inch Reinforced Concrete Pipe	LF	30			30	
······	······································	***************************************	604-00305	Inlet Type C (5 Foot)	EACH	11		***************************************	1	
			606-00302	Guardrail Type 3 (31 Inch Midwest Guardrail System)	LF	188			188	
			606-02003	End Anchorage (Nonflared)	EACH	2			2	
			612-00001	Delineator (Type I)	EACH	5			5	
			612-00003	Delineator (Type III)	EACH	1			1	
			612-00041	Delineator (Flexible) (Type I)	EACH	4			4	
			613-00206	2 Inch Electrical Conduit (Bored)	LF	355			355	
			613-00306	3 Inch Electrical Conduit (Bored)	LF	370			370	
			613-01200	2 Inch Electrical Conduit (Plastic)	LF	55			55	
			613-01300	3 Inch Electrical Conduit (Plastic)	LF	70			70	
			613-07004	Type Four Pull Box	EACH	3			3	
			613-07005	Type Five Pull Box	EACH	1			1	
			613-10000	Wiring	LS	1			1	
		***************************************	613-13000	Luminaire (LED) (Special)	EACH	3			3	
			613-80130	Service Meter Cabinet	EACH	1			1	
			614-00011	Sign Panel (Class I)	SF	18			18	
			614-00012	Sign Panel (Class II)	SF	37			37	
			614-00029	Sign Panel (Class II) (Install Only)	EACH	1			1	
			614-01573	Steel Sign Support (2-1/2 Inch Round NP-40)(Post & Slipbase)	EACH	2			2	
			614-70024	1310nm SFP Optic Module	EACH	2			2	
			614-70336	Traffic Signal Face (12-12-12)	EACH	11			11	
			614-72836	Conflict Monitor	EACH	1			1	
			614-72855	Traffic Signal Controller Cabinet	EACH	1			1	

Print Date: 3/29/22			Sheet Revisions
File Name: I70-SH79_SOAQ.	DWG	Date:	Comments
Horiz. Scale: 0.5:1	Vert. Scale: As Noted		
Unit Information	Unit Leader Initials		
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966		
2000 South Colorado Boulevard	Fax (720) 540-6801		



Init.

As Constructed	SUMMARY OF	Project No./Code			
No Revisions:	QUAN	TITIES	STU 0704-248		
Revised:	Designer: A. MARQUEZ		23180		
	Detailer: M. WAGNER	Numbers	_		
Void:	Sheet Subset: SOAQ	Subset Sheets: 2 of 4	Sheet Number 9		

	INDEX		CONTRACT	CONTRACT ITEM	UNIT	Roadway		PROJECT TOTALS	
воок	PAGE	SHEET	ITEM NO.	CONTRACTITEM	Oldi	PLAN	AS CONST.	PLAN	AS CONST
			614-72866	Fire Preemption Unit and Timer	EACH	3		3	
			614-72887	Microwave Vehicle Radar Detector	EACH	4		4	
			614-81145	Traffic Signal-Light Pole Steel (1-45 Foot Mast Arm)	EACH	3		3	
			614-86248	Traffic Signal Controller (Type 2070LC)	EACH	1		1	
			614-86800	Uninterrupted Power Supply	EACH	1		1	
			614-87010	Fiber Optic Cable (Single Mode) (12 Fiber)	LF	1490		1490	
			614-87012	Fiber Optic Termination Panel (12 Fiber)	EACH	1		1	
			614-87015	Buffer Tube Fan Out Kit	EACH	1		1	
			614-87320	Closed Circuit Television	EACH	1		1	
			614-87350	Test Fiber Optic Cable	LS	1		1	
			614-87512	Splice Fiber Optic Cable (12 Strand)	EACH	1		1	
			614-87692	Ethernet Switch Type II	EACH	1		1	
			620-00002	Field Office (Class 2)	EACH	1		1	
			620-00012	Field Laboratory (Class 2)	EACH	1		1	
			620-00020	Sanitary Facility	EACH	1		1	
			625-00000	Construction Surveying	LS	1		1	
			626-00000	Mobilization	LS	1		1	
			626-01114	Public Information Management (Tier IV)	DAY	150		150	
			627-00008	Modified Epoxy Pavement Marking	GAL	13		13	
			627-30405	Preformed Thermoplastic Pavement Marking (Word- Symbol)	SF	73		73	
			627-30410	Preformed Thermoplastic Pavement Marking (Xwalk-Stop Line)	SF	157		157	
			630-00000	Flagging	HOUR	640		640	
			630-00003	Uniformed Traffic Control	HOUR	640		640	
			630-00006	Uniformed Traffic Control (Vehicle)	HOUR	640		640	
			630-00007	Traffic Control Inspection	DAY	35		35	
			630-00012	Traffic Control Management	DAY	80		80	
			630-80336	Barricade (Type 3 M-B) (Temporary)	EACH	8		8	
			630-80341	Construction Traffic Sign (Panel Size A)	EACH	42		42	
			630-80342	Construction Traffic Sign (Panel Size B)	EACH	17		17	
			630-80355	Portable Message Sign Panel	EACH	6		6	

Print Date: 3/29/22			Sheet Revisions	
File Name: I70—SH79_SOAQ	.DWG	Date:	Comments	Init.
Horiz. Scale: 0.5:1	Vert. Scale: As Noted			
Unit Information	Unit Leader Initials			
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966			
2000 South Colorado Boulevard	Fax (720) 540-6801			



As Constructed	SUMMARY OF	Project No./Code		
No Revisions:	QUAN	TITIES	STU 0704-248	
Revised:	Designer: A. MARQUEZ		23180	
	Detailer: M. WAGNER	Numbers		
Void:	Sheet Subset: SOAQ	Subset Sheets: 3 of 4	Sheet Number 10	

	INDEX		CONTRACT	CONTRACTITEM	LINUT	Roa	dway		PROJEC	T TOTALS
воок	PAGE	SHEET	ITEM NO.	CONTRACT ITEM	UNIT	PLAN	AS CONST.		PLAN	AS CONST.
			630-80360	Drum Channelizing Device	EACH	100			100	
			630-80380	Traffic Cone	EACH	50			50	
			630-80393	Stackable Vertical Panels	EACH	50			50	
			630-85041	Mobile Attenuator	DAY	80			80	
			700-70010	F/A Minor Contract Revisions	FA	1			1	
			700-70016	F/A Fuel Cost Adjustment	FA	1			1	
			700-70380	F/A Erosion Control	FA	1			1	
			700-70589	F/A Environmental Health & Safety Management	FA	1			1	

Print Date: 4/1/22	
File Name: I70-SH79_SOAQ.D	WG
Horiz. Scale: 1:1	Vert. Scale: As Noted
Unit Information	Unit Leader Initials
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000 SEH 2000 South Colorado Boulevard Denver CO 80222-7900	Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

Sheet Revisions					
Date:	Comments	Init.			



TOWN OF BENNETT
207 MUEGGE WAY
BENNETT, CO 80102
TELE. (303) 644-3249
FAX (303) 644-4125

As Constructed	SUMMARY OF APPROXIMATE		SUMMARY OF APPROXIMATE Project No./			
No Revisions:	QUAN	TITIES	STU 0704-248			
Revised:	Designer: A. MARQUEZ		23180			
	Detailer: M. WAGNER	Numbers				
Void:	Sheet Subset: SOAQ	Subset Sheets: 4 of 4	Sheet Number 11			

SUMMARY OF EARTHWORK QU	IANTITIES		
FOR PAY QUANTITY			
UNCLASSIFIED EXCAVATION (COMPLETE IN PLACE)		CUBIC YARDS	
SH 79		354	BCY
I-70 Off-Ramp		1,303	BCY
I-70 On-Ramp		584	BCY
TOTAL FOR P	AY QUANTITY	2,241	BC
FOR INFORMATION ONLY			
EARTHWORK QUANTITIES BALAN	ICE		
EMBANKMENT MATERIAL (COMPLETE IN PLACE)		CUBIC YARDS	
SH 79		38	CC,
I-70 Off-Ramp		723	CC,
I-70 On-Ramp		67	BC/
	TOTAL	828	CC,
<u>NASTE</u>			
EXCAVATED MATERIAL TO BE DISPOSED OF BY CONTRACTOR	₹		
	TOTAL	1,413	BC.
COMPACTION (AASHTO T 99)		CUBIC YARDS	
BASES OF CUTS AND FILLS (8")			CC,
	TOTAL	1,410	CC.
NATER FOR COMPACTION (0.04 MGAL/CUBIC YARD)		CUBIC YARDS	
	TOTAL	56	MG

BCY - BANK CUBIC YARD - ONE CUBIC YARD OF MATERIAL AS IT LIES IN THE NATURAL STATE
CCY - COMPACTED CUBIC YARD - ONE CUBIC YARD OF MATERIAL AFTER IT HAS BEEN COMPACTED TO
SPECIFICATION.

			SURFACIN	GSUMMAR	Y		
		304-06000	403-34871	403-3	3841	412-00850	
STATION TO STATION	SIDE	Aggregate Base Course (Class	Hot Mix Asphalt (Grading SX) (100) (PG 76-28)	Hot Mix Aspha (100) (Po		Concrete Pavement	COMMENT
		6)	2 INCH TOP LIFT	3 INCH MIDDLE LIFT	3 INCH BOTTOM LIFT	(8-1/2 inch)	
		TON	TON	TON	TON	SY	
I-70 Off-Ramp		***************************************	###***********************************				
18+35.68 to 23+83.70	Rt. & Lt.	478				1,575	
SH 79							
102+74.67 to 105+30.67	Rt. & Lt.	434	157	236	236		
I-70 On- Ramp							
50+61.06 to 51+68.88	Rt. & Lt.	133				437	
SU	B-TOTALS	1,045	157	236	236	2,012	
5% IRREGULARITIES AD	JUSTMENT	52	8	12	12	101	
PROJEC	PROJECT TOTALS		165	49	96	2,113	

			TABUL	ATION C	F REMO	VALS, RE	SETS AI	ND ADJU	STMENT	s			
		201-00001	202-00010	202-00090	202-00210	202-00220	202-00700	202-00810	202-00821	202-01130	210-00810	210-01011	210-04020
STATION TO STATION	SIDE	Clearing and Grubbing	Tree	Removal of Delineator	Pavement	Removal of Asphalt Mat	Removal of Light Standard	Ground Sign	Removal of Sign Panel	Removal of Guardrail Type 3	Reset Ground Sign		Modify Inlet
		ACRE	EACH	EACH	SY	SY	EACH	EACH	EACH	LF	EACH	EACH	EACH
I-70 Off Ramp													
18+35.68 to 23+01.58	Rt. & Lt.				1247								
18+35.68 to 24+06.81	Rt & Lt.	0.53											
18+43.11	Rt.							1					
19+37.64	Lt.			1									
19+95.17	Lt.			1							entera, consensation consensation consensation		
20+12.00	Rt. & Lt.										2		
20+94.75	Rt.							*****					1
21+08.12	Lt.			1	M PO STATE M M STATE M M STATE M M M PART M		***			Tananan was announced to the control of the control	***************************************		a de provincia de la provincia de provincia de la provincia dela provincia dela provincia de la provincia de l
21+29.97 to 21+46.51	Rt. & Lt.			***************************************	·····	42							
21+45.32	Rt.								1		1	www.	
21+48.00	Rt. & Lt.			~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~						***************************************	2		
22+04.43	Lt.	***************************************		***************************************	***************************************		***************************************				1		
22+37 to 22+45	Rt.		2										
22+66.34	Lt.			1									
22+94.19	Lt.	***************************************		1				***************************************					······································
23+64.07	Rt.	******************************	•	***************************************			1						
23+71.42	Rt.							2					
23+72.00	Rt. & Lt.	***************************************									2		
23+75.17	Lt.	***************************************						2					
SH 79		************************************					***************************************	***************************************		······································	***************************************		
102+74.67 to 105+30.36		***************************************				1592							
103+77	Lt.			1									
104+33	Lt.		***************************************	1	****						*****************************		
104+34.09 to 105+14.45	Lt.	***************************************								139	***************************************		
104+44.21 to 105+14.77	Rt.						**************			191			
104+81	Lt.	·····		1									
105+20.39	Lt.	***************************************					*******************************			***************************************	1		
				*******************************	***************************************						***************************************		
I-70 On Ramp	[D. C.)												***************************************
50+00.00 to 51+68.88	Rt. & Lt.	0.11			007						***************************************		
50+26.45 to 51+68.88	Rt. & Lt.	***************************************			397			***************************************		Milde Medical Selection and Milde and Milde and Address and Addres			V ************************************
50+39.73	Lt.			1									
50+43.07	Lt.										1		
50+50.30	Lt.										1		
50+60.73	Lt.	***************************************		1									
50+64.14	Rt.						11						
50+72.00	Rt. & Lt.	***************************************				************************************	***************************************				2		***************************************
50+75.74 to 50+77.02	Rt. & Lt.	مسادات والمراجعة والمسيدات والمراجعة والمسيدات										1	
PROJECT	TOTALS	0.64	2	10	1,644	1,634	2	5	1	330	13	1	1
11100201		0.04		טו	1,044	1,004		l J	<u>'</u>	550	13	<u> </u>	<u>'</u>

	TABULATION OF SIGNS									
	PAYITEM								614-01573	
SIGN NUMBER	DACKODOLIND TDAVEL	SIGN PANEL (CLASS II)	STEEL SIGN SUPPORT (2-1/2 INCH ROUND NP- 40) (POST & SLIPBASE)	COMMENTS						
								SF	EACH	
1	W13-2	"EXIT 45 MPH"	YELLOW	3+87.5	RT	EB	36"x48"	12.00	1	
2	W13-3	"RAMP 45 MPH"	YELLOW	15+49.43	RT	WB	48"x48"	16.00		
3	W3-3	SIGNAL	YELLOW	18+43.11	RT	EB	36"x36"	9.00	1	
						PR	OJECT TOTALS	37.00	2	

Print Date: 3/29/22			Sheet Revisions	
File Name: I70-SH79_TAB	ULATIONS.DWG	Date:	Comments	Init.
Horiz. Scale: 0.5:1	Vert. Scale: As Noted			
Unit Information	Unit Leader Initials			
Short Elliott Hendrickson Inc Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966			
2000 South Colorado Boulevard	Fax (720) 540-6801			



As Constructed	TADIII	ATIONS	Project No./Code
No Revisions:	TABUL	ATIONS	STU 0704-248
Revised:	Designer: A. MARQUEZ		23180
	Detailer: M. WAGNER	Numbers	
Void:	Sheet Subset: TABS	Subset Sheets: 1 of 2	Sheet Number 12

TABULATION OF	DRAINA	GE STRU	CTURES	
		603-01240	604-00305	
STATION TO STATION	SIDE	24 Inch Reinforced Concrete Pipe	Inlet Type C (5 Foot)	
		LF		
70 Off-Ramp	1			
20+94.75 to 22+11.71	Rt.	30		
22+11.71	Rt.		1	
PRO	JECT TOTAL	30	1	

		SUMMARY OF	STRIPING		
	PAY ITEM	627-00008	627-30405	627-30210	
COLOR		MODIFIED EPOXY PAVEMENT MARKING	PREFORMED THERMOPLASTIC PAVEMENT MARKING (WORD-SYMBOL)	THERMOPLASTIC PAVEMENT MARKING (X-WALK-STOP LINE)	
		GAL	SF	SF	
WHITE		11	73	157	
YELLOW		2			
PROJECT 1	OTALS	13	73	157	

- 1. APPLICATION RATE FOR EPOXY PAVEMENT MARKING IS ESTIMATED AT 85 SO FT PER GALLON.
- 2. APPLICATION RATE FOR PAVEMENT MARKING PAINT (WATERBORNE) IS ESTIMATED AT 90 SO FT PER GALLON.
- 3. SEE STRIPING PLANS FOR DETAILS.

	TEMPORARY TRAFFIC CONTROL SIGN TABULATION						
SIGN CODE	LEGEND	DIMENSIONS	PANEL SIZE				
SIGN CODE	LEGEND	DIMENSIONS	Α	В	С		
R52-6a	"BEGIN FINES DOUBLE IN WORK ZONE"	36"x48"		3			
W20-1	"ROAD WORK AHEAD"	36"x36"	3				
G20-11	"ROAD WORK MM YY MM YY FOR INFORMATION XXX-XXX-XXX"	48"x48"		3			
W20-4	"ONE LANE ROAD XX FT"	36"x36"	2				
W20-7	FLAGGER	36"x36"	3				
R52-6b	"END FINES DOUBLE IN WORK ZONE"	36"x48"		4			
G20-10	"XYZ CONSTRUCTION THANKS YOU"	48"x48"		4			
W20-2	"DETOUR AHEAD"	36"x36"	3				
M4-10	"DETOUR"	48"x18"	2				
R11-2	"ROAD CLOSED"	48"x30"	1				
E5-2a	"EXIT CLOSED"	"48"x36"		2			
M1-1	"INTERSTATE 70"	36"x36"	7				
M4-8	"DETOUR"	24"x12"	7				
M6-1	Left Arrow Symbol	21"x15"	2				
M6-1	Right Arrow Symbol	21"x15"	2				
M3-3	"EAST"	24"x12"	7				
M4-9r	"DETOUR"	48"x36"		1			
M4-9I	"DETOUR"	30"x24"	3				
	PROJI	ECT TOTALS (2)	42	17			

- (1) TTC Sign Totals are estimates only, Contractor is responsible for Traffic Control Plan
- (2) Sign Totals are estimated based on typical application of CDOT M&S Standard Plan S-630-1, Case No. 19 and Case No. 20, Case No. 23, and I-70 EB Ramp Closure Detour (See Page 29)

ı	DELINEAT	OR SUN	<i>MARY</i>			
		612-0	00001	612-00003	612-00041 Delineator (Flexible) (Type 1)	
STATION ⁽¹⁾	SIDE		eator pe I)	Delineator (Type 3)		
		Crystal	Yellow	Yellow	Yellow	
		EACH	EACH	EACH	EACH	
I-70 Off Ramp)					
19+37.96	LT		1			
20+36.63	LT		1			
21+36.40	LT		1			
22+37.98	LT		1			
23+60.41	LT			1		
SH 79						
103+74.14	LT	1				
104+24.63	LT				1	
104+48.17	LT				1	
I-70 On Ramp)					
50+50.99	LT				1	
50+74.87	LT				1	
PROJECT TOTALS		;	5	1	4	

(1) Locations are approximate. Refer to Standard Plan S-612-1 for locations/layout of delineators.

Print Date: 3/29/22		Sheet Revisions		
File Name: I70-SH79_TABULATIONS.DWG		Date:	Comments	Init.
Horiz. Scale: 0.5:1	Vert. Scale: As Noted			
Unit Information	Unit Leader Initials			



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

As Constructed	TADII	ATIONS	Project No./Code
No Revisions:	TABU	LATIONS	STU 0704-248
Revised:	Designer: A. MARQUEZ	Structure	23180
	Detailer: M. WAGNEF	Numbers	
Void:	Sheet Subset: TABS	Subset Sheets: 2 of 2	Sheet Number

STATION TO STATION	MODIFIED EPOXY PAVEMENT MARKING		THERMOPLASTIC PAVEMENT MARKING (WORD-SYMBOL)	THERMOPLASTIC PAVEMENT MARKING (XWALK- STOPLINE)	
CON TO STATION		CENTER LINE DOUBLE YELLOW, 4 INCH	EDGE LINE, SOLID WHITE 6 INCH	RAMP PAVEMENT ARROW	STOP BAR WHITE 2' WIDE
		SF	SF	SF	SF
I-70 Off-Ramp					
20+03.00	Lt.			24.3	
21+40.00	Lt.			24.3	
23+60.00	Lt.			24.3	
18+35.68 to 24+08.81	Rt. & Lt.		650		
23+82.09	Rt. & Lt.				96
SH 79					
102+74.67 to 103+59.21	Rt. & Lt.	56			
103+59.21	Rt.				37
104+54.11	Lt.				24
104+54.11 to 105+30.36	Rt. & Lt.	51			
I-70 On-Ramp					
50+00.00 to 51+68.88	Rt. & Lt.		241		

890

TABULATION OF STRIPING

627-00008

627-30405

PREFORMED

73

EACH

EACH

DAY

50

50

80

627-30410 PREFORMED

THERMOPLASTIC

157

PAY ITEM

PROJECT TOTAL (SF)

ITEM NO.	ITEM	UNIT	PROJECT TOTALS ⁽¹⁾
630-00000	FLAGGING	HOUR	640
630-00003	UNIFORMED TRAFFIC CONTROL	HOUR	640
630-00006	UNIFORMED TRAFFIC CONTROL (VEHICLE)	HOUR	640
630-00007	TRAFFIC CONTROL INSPECTION	DAY	35
630-00012	TRAFFIC CONTROL MANAGEMENT	DAY	80
630-80336	BARRICADE (TYPE 3 M-B) (TEMPORARY)	EACH	8
630-80341	CONSTRUCTION TRAFFIC SIGN (PANEL SIZE A)	EACH	42
630-80342	CONSTRUCTION TRAFFIC SIGN (PANEL SIZE B)	EACH	17
630-80355	PORTABLE MESSAGE SIGN PANEL	EACH	6
630-80360	DRUM CHANNELIZING DEVICE	EACH	100

107

TEMPORARY TRAFFIC CONTROL SUMMARY

(1) TTC estimates assume one active closure at a time.

STACKABLE VERTICAL PANELS

TRAFFIC CONE


630-85041 MOBILE ATTENUATOR

630-80380


630-80393


Print Date: 3/29/22

Short Elliott Hendrickson Inc. Colorado Center Tower One



X:\AE\B\BENNT\58279\Bennett Interchande Design\Design\Drawings\170-SH79 Removal Plan.dwg 3/15/2022 3:52 PM k</br>







OUTSIDE EDGE OF TRAVEL PROFILE

Print Date: 3/29/22			Sheet Revisions	
File Name: I70-SH79_ROADW	/AY P&P_02.DWG	Date:	Comments	Init.
Horiz. Scale: 0.5:1	Vert. Scale: As Noted			
Unit Information	Unit Leader Initials			
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000 Suite 6000	Tele. (720) 540-6800 (800) 490-4966			



As Constructed	ROADWAY PLAI	N AND PROFILE	Project No./Code
No Revisions:	I-70 EB	STU 0704-248	
Revised:	Designer: A. MARQUEZ	Structure	23180
	Detailer: K. KULESZA	Numbers	
Void:	Sheet Subset: P&P	Subset Sheets: 2 of 3	Sheet Number 17






CENTERLINE PROFILE

Print Date: 3/29/22			Sheet Revisions	
File Name: I70-SH79_ROADWAY P&P_03.DWG		Date:	Comments	Init.
Horiz. Scale: 0.5:1 Vert.	Scale: As Noted			
Unit Information Un	it Leader Initials			
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966			
2000 South Colorado Boulevard	Fax (720) 540-6801			1



As Constructed	ROADWAY PLAN	Project No./Code	
No Revisions:	SH	STU 0704-248	
Revised:	Designer: A. MARQUEZ	Structure	23180
	Detailer: K. KULESZA	Numbers	
Void:	Sheet Subset: P&P	Subset Sheets: 3 of 3	Sheet Number 18



X-AEIRIBENNT158279\Bennett Interchange Design\Design\Drawings\\70-SH79 Intersection Plan dwg 3/1/2022 2-16


X:AE\B\BENNT\158279\Bennett Interchange Design\Design\Drawings\tag{170-SH79} Storm Drain P&P.dwg 3/30/2022 9:21 AM kdlunis

TRAFFIC SIGNAL GENERAL NOTES

- 1. TRAFFIC SIGNAL MATERIALS AND INSTALLATION SHALL COMPLY WITH THE "STATE OF COLORADO—STANDARD PLANS, M AND S STANDARDS (LATEST EDITION), THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES", THE "NATIONAL ELECTRIC CODE" (LATEST EDITION) AND ALL LOCAL ORDINANCES AND REGULATIONS THAT APPLY, EXCEPT AS NOTED ON THE PLANS OR SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL EXISTING AERIAL AND UNDERGROUND UTILITIES AND THE PROTECTING OF THESE UTILITIES. LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE AND NOT ALL UTILITIES ARE NECESSARILY SHOWN. THE CONTRACTOR SHALL CONTACT ALL THE APPROPRIATE ENTITIES TO LOCATE UNDERGROUND FACILITIES AT LEAST 48 HOURS PRIOR TO COMMENCEMENT OF CONSTRUCTION. THE EXACT LOCATION OF EACH UTILITY SHALL BE FIELD VERIFIED BEFORE COMMENCING WORK. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MAY OCCUR AS A RESULT OF THE CONTRACTOR'S FAILURE TO LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. LOCATIONS OF THE TRAFFIC SIGNAL LIGHT POLES AND PEDESTAL POLE FOUNDATIONS SHALL BE ADJUSTED BY THE ENGINEER IF NECESSARY.
- 3. THE PHYSICAL FEATURES WITHIN THE LIMITS OF THE PROJECT HAVE BEEN SHOWN BASED ON THE BEST AVAILABLE INFORMATION AT THE TIME OF DESIGN. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THE FEATURES SHOWN. THE CONTRACTOR SHALL REVIEW AND VERIFY EXISTING PHYSICAL FEATURES AND INFORM HIMSELF OF THE CONDITIONS TO BE ENCOUNTERED DURING CONSTRUCTION.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL PERMITS/INSPECTIONS REQUIRED TO COMPLETE THE SCOPE OF WORK PRESENTED HEREIN.
- 5. ALL ITEMS NOT SHOWN IN THE SUMMARY OF APPROXIMATE QUANTITIES SHALL BE CONSIDERED INCIDENTAL TO THE INSTALLATION OF THE TRAFFIC SIGNAL AND WILL NOT BE MEASURED AND PAID FOR SEPARATELY. ALL QUANTITIES ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK NECESSARY TO COMPLETE THE CONSTRUCTION SHOWN ON THESE PLANS. MEASUREMENT AND PAYMENT OF TRAFFIC SIGNALS CONSTRUCTION ITEMS SHALL CONFORM TO THE PROJECT SPECIFICATIONS.
- 6. PULL BOX LOCATIONS ARE APPROXIMATE. ACTUAL LOCATIONS SHALL BE VERIFIED IN THE FIELD BY THE ENGINEER. ALL PULL BOXES SHALL BE FLUSH WITH FINISHED GROUND SURFACE.
- 7. ALL PULL BOXES, INCLUDING THOSE FOR WHICH COST IS INCLUDED IN THE COST OF CONDUIT ITEMS, SHALL BE FABRICATED PER PROJECT SPECIAL PROVISION 613 PULL BOX.
- 8. THE SIGNAL SHALL NOT BE PUT IN FLASH MODE OR MADE FULLY OPERATIONAL UNTIL CDOT HAS INSPECTED AND APPROVED THE INSTALLATION AND ALL REGULATORY SIGNING AND PAVEMENT MARKINGS ARE IN PLACE. INCH PREFORMED JOINT MATERIAL SHALL BE APPLIED AROUND THE 6 INCHES OF LEVELING CONCRETE BENEATH SIGNAL POLES WHEN THE SIGNAL POLE IS INSTALLED IN EXISTING CONCRETE AND CONSIDERED INCIDENTAL TO THE WORK AND SHALL NOT BE PAID FOR SEPARATELY.
- 9. ANY DAMAGES INCURRED DURING CONSTRUCTION ACTIVITIES INCLUDING BUT NOT LIMITED TO LANDSCAPING, SIDEWALKS, CURB AND GUTTER, CONCRETE RAMPS AND SIGNS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO BE REPAIRED OR REPLACED AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AT HIS EXPENSE.
- 10. WASTE MATERIALS GENERATED BY THE CONTRACTOR SHALL BE DISPOSED OF BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE PROJECT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN A LEGAL DISPOSAL SITE FOR ALL UNUSABLE MATERIALS.
- 11. CONTRACTOR'S SIGNAL ELECTRICIAN IS REQUIRED TO BE ON SITE, AT A MINIMUM, DURING AM & PM PEAK HOURS FOLLOWING THE NEXT DAY A SIGNAL IS TURNED ON TO OBSERVE OPERATION AND MAKE ADJUSTMENTS AS NEEDED. THE ENGINEER MAY REQUIRE THE SIGNAL ELECTRICIAN TO BE ONSITE FOR ADDITIONAL HOURS AS DIRECTED. THIS APPLIES TO BOTH PERMANENT AND TEMPORARY INSTALLATIONS.
- 12. SHOULD CONTRACTOR ENCOUNTER WATER IN CAISSON, ANY DE-WATERING METHODS & NECESSARY PERMITS SHALL BE INCLUDED IN
 THE COST OF CAISSON.
- 13. A JOURNEYMAN ELECTRICIAN SHALL BE ON SITE AT ALL TIMES DURING ELECTRICAL TRAFFIC SIGNAL WORK INCLUDING INSTALLATION OF CONDUITS. THE CONTRACTOR SHALL ADHERE TO THE FOLLOWING REQUIREMENTS REGARDING TRAFFIC SIGNAL CONSTRUCTION AND MAINTENANCE PERSONNEL. CURRENT CERTIFICATES SHOWING QUALIFICATIONS SHALL BE SUBMITTED AT THE PRE—CONSTRUCTION MFFTING.
 - (1) FOR ANY WORK INSIDE THE TRAFFIC SIGNAL CABINET, SIGNAL AND SIGNAL BENCH TECHNICIANS SHALL BE MINIMUM IMSA LEVEL II CERTIFIED. THIS INCLUDES THE COMPLETION OF TRAINING IN CONSTRUCTION, CORRECTIVE MAINTENANCE, AND SIGNAL TURN-ON.
 - (2) FIELD TECHNICIAN/ELECTRICIAN OR TRAFFIC SIGNAL BENCH TECHNICIAN/SIGNAL TECHNICIAN IS REQUIRED. AN IMSA LEVEL II TRAFFIC SIGNAL ELECTRICIAN SHALL BE ON THE JOB SITE AT ALL TIMES THAT SIGNALIZATION WORK IS TAKING PLACE TO ENSURE PROPER CONSTRUCTION.
 - A MAXIMUM RATIO OF FOUR IMSA LEVEL I TO ONE IMSA LEVEL II WILL BE ALLOWED FOR WORK EXTERNAL TO THE SIGNAL CABINET.THE UNITED STATES DEPARTMENT OF LABOR BUREAU OF APPRENTICESHIP AND TRAINING MAY BE SUBSTITUTED FOR THE IMSA LEVEL I TRAFFIC SIGNAL ELECTRICIAN REQUIREMENT.
- 4. ITEM 613-10000, WIRING (1 LUMP SUM), SHALL INCLUDE ALL NECESSARY WIRING WORK, NOT OTHERWISE INCLUDED IN AN INDIVIDUAL PAY ITEM, REQUIRED TO PROVIDE A COMPLETE AND FULLY FUNCTIONAL TRAFFIC SIGNAL SYSTEM.
- 15. THE LOCATION OF TRAFFIC SIGNAL EQUIPMENT INCLUDING CONTROLLER CABINETS, POLES, AND PULL BOXES WITHIN CDOT ROW SHALL BE FIELD VERIFIED WITH TONY REED, CDOT REGION 1 TRAFFIC SIGNALS/RAMP METERING, AT 720-737-6807 AND TONY.REED@STATE.CO.US PRIOR TO CONSTRUCTION. SIGNAL DETECTION SHALL BE FIELD VERIFIED WITH THE VENDOR AND TONY REED PRIOR TO CONSTRUCTION.

TRAFFIC SIGNAL GENERAL NOTES (CONT.)

- 16. OPEN EXCAVATIONS SHALL NOT BE ALLOWED UNPROTECTED WHEN CONSTRUCTION WORK IS NOT IN PROGRESS (INCLUDING OVERNIGHT, WEEKENDS AND HOLIDAYS). METHOD(S) OF PROTECTING EXCAVATIONS (IE METAL PLATES OR CONCRETE BARRIER) FROM VEHICLES AND PEDESTRIANS SHALL BE APPROVED BY THE ENGINEER. THE COST OF PROTECTING EXCAVATIONS WILL NOT BE MEASURED AND PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE WORK.
- 17. TWO OR MORE WEEKS PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT TEMPORARY PHASING AND TIMING SIGNAL PLANS TO THE ENGINEER FOR APPROVAL.
- 18. UPON COMPLETION OF THE WORK, THE CONTRACTOR SHALL SUPPLY 2 SETS OF RECORD DRAWINGS, CORRECTED PLANS AND ANY OTHER ADDITIONAL DATA REQUIRED BY THE ENGINEER TO THE ENGINEER.
- 9. THE CONTRACTOR SHALL PROVIDE CDOT WITH AT LEAST FOUR (4) SETS OF EQUIPMENT SPECIFICATIONS/DESCRIPTIONS AND OBTAIN APPROVALS PRIOR TO ORDERING THE EQUIPMENT.
- 20. ALL MANUALS, INSTALLATION GUIDES AND ASSOCIATED EQUIPMENT SHALL BE PROVIDED TO THE ENGINEER AT TIME OF INSPECTION.
- 21. CONTROLLER CABINET SHALL BE AS SHOWN ON THE PLANS AND SHALL BE INCLUDED IN THE COST OF THE CONTROLLER. THE CONTROLLER CABINET SHALL BE MOUNTED ON A PREFORMED CONCRETE BASE. LOAD SWITCHES SHALL INDICATE INPUT AND OUTPUT THE UNINTERRUPTIBLE POWER SUPPLY (UPS) SHALL BE PROVIDED TO RUN SIGNAL FOR 2 HOUR IN ALL PHASES, AND FLASH UP TO FOUR ADDITIONAL HOURS.
- 22. CAISSON LOCATIONS SHALL BE MARKED, POTHOLED IF NECESSARY FOR CONFLICTING UTILITIES, AND FIELD VERIFIED BY THE PROJECT ENGINEER PRIOR TO ORDERING MAST ARMS. 20 HOURS OF POTHOLING IS ESTIMATED FOR THIS PROJECT.
- 23. THE CONTRACTOR SHALL OBTAIN AN ELECTRICAL PERMIT FROM THE COLORADO STATE ELECTRICAL BOARD (DORA) FOR ALL ELECTRICAL AND TRAFFIC SIGNAL WORK.
- 24. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING AND MAINTAINING ADEQUATE TRAFFIC CONTROL THROUGHOUT THE PROJECT, INCLUDING PROPER TRAFFIC CONTROL DEVICES AND PERSONNEL. TRAFFIC CONTROL IS TO BE IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
- 25. ALL SIGNAL DETECTION SHOWN ON PLANS IS FOR ILLUSTRATIVE PURPOSES ONLY. ONE STOP BAR DETECTION UNIT AND THREE ADVANCE DETECTION UNITS ARE ESTIMATED.
- 26. TRAFFIC SIGNAL POLES SHALL BE A MINIMUM OF 40' IN HEIGHT FROM THE FINISHED GRADE. TRAFFIC SIGNAL POLES SHALL BE HOT DIP GALVANIZED STEEL.
- 27. FIRE PREEMPTION UNITS SHALL BE FURNISHED, TESTED, AND APPROVED BY THE LOCAL FIRE AUTHORITY.





As Constructed	TDAEEIC SIC	SNAL NOTES	Project No./Code
No Revisions:	INAFFIC SIG	STU 0704-248	
Revised:	Designer: A. MARQUEZ	Structure Numbers	23180
Void:	Detailer: M. WAGNER Sheet Subset: SIGNAL	Subset Sheets: 1 of 6	Sheet Number 22

TABULATION OF TRAFFIC SIGNAL ITEMS							
			1-70	EB RAMPS & S	H 79		
CONTRACT ITEM NO.	CONTRACT ITEM DESCRIPTION	UNIT	NE	SE	sw	TOTAL QUANTITY	
TI CINITIO			QTY	QTY	QTY	_ doz.	
503-00036	Drilled Shaft (36 Inch)	LF	19	19	19	57	
613-00206	2 Inch Electrical Conduit (Bored)	LF		90	95	185	
613-00306	3 Inch Electrical Conduit (Bored)	LF		180	190	370	
613-01200	2 Inch Electrical Conduit (Plastic)	LF	10	10	25	45	
613-01300	3 Inch Electrical Conduit (Plastic)	LF	20	20	30	70	
613-07004	Type Four Pull Box	E A CH	1	1	1	3	
613-10000	Wiring	LS				1	
613-13000	Luminaire (LED) (Special)	EACH	1	1	1	3	
613-80130	Service Meter Cabinet	EACH			1	1	
614-00011	Sign Panel (Class I)	SF	9		9	18	
614-00029	Sign Panel (Class II) (Install Only)	EACH		1		1	
614-70336	Traffic Signal Face (12-12-12)	EACH	4	4	3	11	
614-72855	Traffic Signal Controller Cabinet	EACH			1	1	
614-72866	Fire Preemption Unit and Timer	EACH	2	1		3	
614-72887	Microwave Vehicle Radar Detector (Stop Bar Detection)	EACH	1	1	1	_	
614-72887	Microwave Vehicle Radar Detector (Advanced Detection)	EACH	1		1	5	
614-81145	Traffic Signal-Light Pole Steel (1-45 Foot Mast Arm)	EACH	1	1	1	3	
614-86248	Traffic Signal Controller (Type 2070LC)	EACH			1	1	
614-86800	Uninterrupted Power Supply	EACH			1	1	
614-87320	Closed Circuit Television	EACH		1		1	


Print Date: 3/29/22	
File Name: I70-SH79_SIGNAL	PLAN.DWG
Horiz. Scale: 0.5:1	Vert. Scale: As Noted
Unit Information	Unit Leader Initials
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000 SEH 2000 South Colorado Boulevard Denver, CO 80222-7900	Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

Sheet Revisions			
Date: Comments In			



As Constructed	TRAFFIC SIGNA	Project No./Code	
No Revisions:	INAFFIC SIGNA	STU 0704-248	
Revised:	Designer: A. MARQUEZ Structure		23180
Void:	Detailer: M. WAGNER Sheet Subset: SIGNAL	Subset Sheets: 2 of 6	Sheet Number 23





LEGEND

TRAFFIC SIGNAL CONTROLLER & CABINET PULL BOX (TYPE 4 UNLESS NOTED)

EMERGENCY VEHICLE PREEMPTION (EVP)

LUMINAIRE

SIGNAL HEAD

MAST ARM (LENGTH AS SPECIFIED)

сст∨⊲

CLOSED CIRCUIT TELEVISION

UNDERGROUND CONDUIT

SIGNAL HEAD WITH BACKPLATE

 \Box

Print Date: 3/29/22

Horiz. Scale: 0.5:1

Unit Information

File Name: I70-SH79_SIGNAL PLAN.DWG

Short Elliott Hendrickson Inc Colorado Center Tower One

MAST ARM MOUNTED SIGN

 \Box^{EM} ELECTRIC SERVICE METER CABINET

MICROWAVE VEHICLE RADAR DETECTOR

SIGN DETAILS

SH 79

D3-1 (INSTALL ONLY)





(36"x36")



(36"x36")

Vert. Scale: As Noted

Unit Leader Initials

Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

SIGNAL HEAD DETAIL

N/A

ø1

N/A

ø5

PHASE DIAGRAM

ø2

ø6

N/A

ø3

N/A

ø7

ø4


N/A

ø8

Init.

(1)

	1		2
2" (R	12"	R
2" (Y	12"	(
2" (G	12"	(6



	V	(
	0	10 20		
le		feet		
le	5	ieet		
		Sheet Revisions		
	Date:	Comments		
`			\neg	

TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

ø6 ADVANCED DETECTION-

ø6 STOP BAR DETECTION-

|04 STOP BAR DETECTION

© CCTV □

 $\langle 3 \rangle$

1-2" |2-3"

1-70 EB OFF-RAMP

SH

2

_1-2" 2-3"

2 2

45' MA

SH

45' MA

1 3

1-2"_ 2-3"

1) -

1-2"

2-3"

-ø2 STOP BAR DETECTION

-ø2 ADVANCED DETECTION

1-70 EB ON-RAMP

\ \ \			
As Constructed	TRAFFIC SIGNAL PLAN		Project No./Code
No Revisions:	TRAFFIC SI	GNAL FLAN	STU 0704-248
Revised:	Designer: A. MARQUEZ Detailer: M. WAGNER	Structure Numbers	23180
Void:	Detailer: M. WAGNER Sheet Subset: SIGNAL		Sheet Number 24




SEE INTERCONNECT

PLAN FOR MORE DETAILS

TYPE 5 FIBER PULL BOX

(SEE INTERCONNECT PLAN)

N	
N	
0	
Ø	
Ø.	
/16/2	
3	
-	
δ,	
≥	
o.	
_	
<u>a</u>	
Δ.	
-	
<u>a</u>	
Ε.	
٠,٠	
W)	
ı70-SH79_Sign	
δ.	
÷	
六	
ų	
Ó	
_	
7	
35	
۶,	
₹	
2	
Ø	
靣	
2	
듬	
,	
χ	
ĕ	
Ō	
<u>.</u>	
S	
Φ	
Φ	
Ď	
⊆′	
g	
'	
2	
ø	
Ξ	
t Interd	
je i	
⊨	
<u>~</u>	
m	
9	



<u>NOTES</u>

- 1. See Standards M-613-1, S-614-40 AND S-614-43 for Meter, Luminaire, Pull box and Traffic Signal details.
- 2. Payment of luminaires shall be as shown on the plans.
- 3. FOR STREET LIGHT LUMINAIRES ON SPAN WIRE INSTALLATIONS—
 Two (2) number 12 AGW copper TW insulated building wires shall be installed by the contractor from the end of the luminaire arm, through the pole, along the span wire cable to the signal pole nearest the controller cabinet, through the pole, then to the power source.
- 4. FOR STREET LIGHT LUMINAIRES ON MAST ARM INSTALLATIONS

 Two (2) number 12 AGW copper TW insulated building wires shall be installed by the contractor from the end of the luminaire arm, through the pole to the pull box at the base of the signal pole. The contractor shall also install the same size wiring from the pull box at the base of the signal pole, through the conduit network, to the power source.
- All wiring for luminaires shall be included in the work and not paid for separately.
- 6. All splices at the power source shall be done by the Power Company $\,$
- 7. Wiring for street light luminaires shall be tagged per project special provision, Revision of Section 613 Electrical Conductor Identification
- 8. 10 feet of extra wire shall be coiled at the base of the power source.


LEGEND

- 3 Inch Electrical Conduit (SCH 80) for loop detector wire, pedestrian push button wire and communication lines.
- ▲ 3 Inch Electrical Conduit (SCH 80) for traffic signal field electrical wire communication lines.
- 2 Inch Electrical Conduit (SCH 80) for luminaire wiring
- Shall have the word "TRAFFIC" engraved into lid
- Shall have the word "ELECTRIC" engraved into lid. These Pull Boxes shall not be paid for separately but shall be paid for under Specification
- 613.12 of the Colorado Department of Transportation "Standard Specification for Road and Bridge Construction"

Print Date: 3/29/22			Sheet Revisions	
File Name: I70-SH79_SIGNA	L PLAN.DWG	Date:	Comments	Init.
Horiz. Scale: 1:1	Vert. Scale: As Noted			
Unit Information	Unit Leader Initials			
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966			
2000 South Colorado Boulevard	Fax (720) 540-6801			



As Constructed	TRAFFIC SIGNAL ELECTRICAL DETAIL		Project No./Code	
No Revisions:			STU 0704-248	
Revised:	Designer: A. MARQUEZ Structure		23180	
Void:	Detailer. W. WAONER	Numbers Subset Sheets: 4 of 6	Sheet Number 25	



ELECTRICAL DNE-LINE DIAGRAM

SH 79 & I-70 EB RAMPS


NO SCALE

Print Date: 3/29/22	
File Name: I70-SH79_SI	GNAL PLAN.DWG
Horiz. Scale: 1:1	Vert. Scale: As Noted (
Unit Information	Unit Leader Initials (
Short Elliott Hendrickson Ir Colorado Center Tower One Suite 6000 2000 South Colorado Boulevard Denver, CO 80222-7900	Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

Sheet Revisions			
Date:	Comments	Init.	



As Constructed	TDAFFIC SIGNAL	Project No./Code	
No Revisions:	TRAFFIC SIGNAL 1-LINE DIAGRAM -		STU 0704-248
Revised:	Designer: A. MARQUEZ Structure Detailer: M. WAGNER Numbers		23180
Void:	Detailer: M. WAGNER Sheet Subset: SIGNAL	Subset Sheets: 5 of 6	Sheet Number 26



X;AE/B/BENNT/158279/Bennett Interchange Design/Design/Drawings/170-SH79 Interconnect! Plan.dwg 3/3/2022 8:37 AM miwagne

welcome neighbors.

Revised:

Void:

23180

Sheet Number

28

K. KULESZA Numbers

Sheet Subset: S&S PLAN Subset Sheets: 1 of 3

Unit Information

Short Elliott Hendrickson Inc Colorado Center Tower One

Unit Leader Initials

Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

X:AEIBIBENNT/158279\Bernett Interchange Design/Design/Drawings\70-SH79 Signing&Striping Plan.dwg 3/15/2022 4:22 PM kdunis

X:AE\B\BENNT\58279\Bennett Interchange Design\Design\Drawings\I70-5H79 Signing&Striping Plan.dwg 3/15/2022 4:22 PM kdun

30M4-9I

LEGEND

ROAD CLOSURE AREA



PORTABLE VMS LOCATIONS TO BE PLACED AS DIRECTED BY THE ENGINEER

NOTES

VMS (1) ON EB I-70, WEST OF MANILLA RD VMS (2-5) ON SH 79 VMS (6) ON SH 36

24M3-2

36M1-1

THIS IS A DEPICTION OF THE DETOUR ROUTE, NOT ALL SIGNS NEEDED FOR THIS DETOUR ARE DISPLAYED IN THIS PLAN. MHT WILL NEED TO BE SUBMITTED AND APPROVED BY THE ENGINEER BEFORE STARTING CONSTRUCTION.

24M4-8 21M6-1

SH 36 TO STRASBURG -

BENNETT I-70 EB RAMP CLOSURE DETOUR

Project No./Code STU 0704-248

Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

EAST

24M3-2

36M1-1

24M4-8

welcome neighbors.

EAST

DETOUR

TOWN OF BENNETT

24M3-2

36M1-1

24M4-

SWMP TEMPLATE (PLAN SHEETS) FOR PROJECTS WITH LESS THAN 1 ACRE OF DISTURBANCE (5/6/2021)

1. SITE DESCRIPTION

The Contractor shall comply with all CDOT contractual requirements. The SWMP Administrator for Construction shall update to reflect current project site conditions.

1. PROJECT SITE LOCATION: Location or address of construction office: I-70 Eastbound Ramps and SH 79 in Bennett, CO.

B. PROJECT SITE DESCRIPTION:

This interchange and intersection improvement project includes re-aligning the eastbound exit ramp and installing a new signal at the intersection. Additionally, this project includes installing a new storm drain system to collect the runoff in this area. Minor grading will be required on the sides of the re-aligned exit ramp. This project is designed to be incorporated in a larger interchange improvement project that will see the SH 79 bridge over I-70 being replaced and widened.

C. PROPOSED SEQUENCING FOR MAJOR CONSTRUCTION ACTIVITIES: clearing and grubbing, grading, drainage, and excavation.

D. ACRES OF DISTURBANCE:

- 1. Total area of construction site (LOC): 1.31 acres
- 2. Total area of proposed disturbance (LDA): 0.64 acres
- 3. Total area of seeding: 0.60 acres
- E. EXISTING SOIL DATA Weld-Deertail complex, 0 to 3 percent slopes (4.5%), Weld-Deertail silt loams, 0 to 3 percent slopes (95.5%)

Data Source(s): %) https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm

F. EXISTING VEGETATION, INCLUDING PERCENT OF VEGETATIVE COVER: During design, the SWMP Administrator for Design in consultation with the Engineer will determine if the SWMP Administrator for Design or the SWMP Administrator for Construction will conduct the Vegetation Transects. If the site is disturbed, an Adequate Reference Site(s) may be utilized, refer to the permit.

<u>Pre-Construction</u> Date of survey:	Percent Existing Vegetative Cover:
Description of existing vegetation:	
Method for determining percent vegetative	cover:
nclude a man or table showing transect loc	cations, photos documentina pre-Co

Include a map or table showing transect locations, photos documenting pre-Construction vegetative cover, and methodology used to determine existing vegetative cover to SWMP tab 17:

Post-Construction Date of survey: ______ Percent Vegetative Cover: _ Description of vegetation:

The method used to determine pre-construction percent cover shall be used to determine post construction

Include map or table showing transect locations, photos documenting post-Construction vegetative cover, and methodology used to determine existing vegetative cover to SWMP tab 17:

2. STORMWATER MANAGEMENT CONTROLS FOR FIRST CONSTRUCTION ACTIVITIES

THE CONTRACTOR SHALL PERFORM THE FOLLOWING:

A. POTENTIAL POLLUTANT SOURCES

1. Refer to Potential Pollutant Sources in SWMP Section 4A. Evaluate, identify and describe all potential sources of pollutants at the site in accordance with subsection 107.25 and place any Control Measures required to contain potential pollutants.

B. OFFSITE DRAINAGE (RUN ON WATER)

1. Place Control Measures to address run-on water in accordance with subsection 208.03.

C. CONSTRUCTION DEWATERING:

Print Date: 3/29/22 Sheet Revisions File Name: I70-SH79_SWMP.DWG Date: Comments Init. Horiz. Scale: 0.5:1 Vert. Scale: As Noted Unit Information Unit Leader Initials Short Elliott Hendrickson Inc Colorado Center Tower One



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

1. Obtain a CDPS Dewatering Permit from CDPHE if conditions of their Low Risk Guidance for Discharges of Uncontaminated Groundwater to Land are not met; see subsections 107.02 and 107.25.

Refer to CDPHE Low Risk Discharge Guidance Document of Uncontaminated Groundwater to Land.

D. VEHICLE TRACKING CONTROL

1. Control Measures shall be implemented in accordance with subsection 208.04.

https://www.colorado.gov/pacific/sites/default/files/WQ%20LOW%20RISK%20GW.pdf

E. PERIMETER CONTROL

- 1. Perimeter control shall be established as the first item on the SWMP to prevent the potential for pollutants leaving the construction site boundaries, entering the stormwater drainage system, or discharging to
- 2. Perimeter control may consist of berms, silt fence, erosion loas, existing landforms, or other Control Measures as approved.

3. QUALIFIED STORMWATER MANAGERS:

A. SWMP ADMINISTRATOR FOR DESIGN: CDOT Certified Individual responsible for developing SWMP Plan Sheets and SWMP Site Maps during the design phase.

Name/Title	Contact Information	Certification #
Katie Croell	303-586-5814	A34F8036
Engineer	kcroell@sehinc.com	

2. SWMP ADMINISTRATOR FOR CONSTRUCTION: (As defined in Subsection 208) The Contractor shall designate a SWMP Administrator for Construction. The SWMP Administrator for Construction shall become the operator for the SWMP and assume responsibility for all design changes to the SWMP implementation and maintenance in accordance to 208.03, the SWMP shall remain the property of CDOT. The SWMP Administrator for Construction shall be responsible for implementing, maintaining and revising SWMP, including the title and contact information. The activities and responsibilities of the SWMP Administrator for Construction shall address all aspects of the project's SWMP. (Update the information below for each new SWMP Administrator for Construction) (Copy of TECS Certification must also be included in the SWMP.)

Name/Title	Contact Information (phone & email)	TECS Certification #	Start Date	Engineer Approval

- 3. PERMANENT STABILIZATION SUBJECT MATTER EXPERT: This qualified individual will be either a Regional Environmental Staff member, or an Independent Contractor Controller (Independent Assurance Program). This expert is a project team leader responsible for ensuring project adherence to requirements of the 207 and 212 Project Special Provisions as follows, and will be available for questions regarding permanent stabilization requirements.
 - 1. Review the Topsoil Management Plan and the Permanent Stabilization Site Maps.
 - 2. Attend the Environmental Pre-construction Conference.
 - Coordinate the Site Pre-vegetation Conference.
 - Review and recommend approval of products.
 - 5. Review and recommend approval of the Quantities Verification Prerequisite.
 - 6. Attend the Substantial Landscape Completion Walkthrough.
 - 7. Attend the Final Landscape Completion Walkthrough.

Name/Title	Contact Information [phone & email]

4. DURING CONSTRUCTION

The SWMP should be considered a "living document" that is continuously reviewed and modified. During construction, the following items shall be added, updated, or amended as needed by the Contractor in accordance with Section 208

As Constructed	STORMWATER MA	Project No./Code		
No Revisions:	1 STORMWATER MA	STU 0704-248		
Revised:	Designer: A. MARQUEZ	Structure	23180	
	Detailer: M. WAGNER	Numbers		
Void:	Sheet Subset: SWMP	Subset Sheets: 1 of 6	Sheet Number	32

- A. MATERIALS HANDLING AND SPILL PREVENTION: prior to construction commencing the Contractor shall submit a Spill Prevention, Control and Countermeasure Plan, see subsection 208.06. Materials handling shall be in accordance with subsection 208.06.
- B. OTHER CDP\$ PERMITS: List applicable CDP\$ permits associated with the permitted site and activities.
- C. STOCKPILE MANAGEMENT: shall be done in accordance with subsections 107.25 and 208.07
- D. CONCRETE WASHOUT: Concrete wash out water or waste from field laboratories and paving equipment shall be contained in accordance with subsection 208.05.
- E. SAW CUTTING: shall be done in accordance with subsections 107.25, 208.04, 208.05
- F. STREET SWEEPING: shall be done in accordance with subsection 208.04

5. CONTROL MEASURE MAINTENANCE

A. Maintenance shall be in accordance with subsection 208.04 (f).

6. INTERIM AND PERMANENT STABILIZATION

The Contractor shall comply with all interim stabilization and permanent stabilization requirements in accordance with subsection 208.04(e).

A. SEEDING PLAN

The following seed mix(es) and rates are for drill seeding method as shown on the Permanent Stabilization Site Maps shall be used:

COMMON NAME	BOTANICAL NAME	LBS. PLS PER ACRE
Sideoats gramma	Bouteloua Curtipendula var. Vaughn	2.7
Blue grama	Bouteloua Gracilis var. Lovington	1.1
Mountain brome	Bromus Marginatus var. Witmar	5.0
Canada Wildrye	Elymus Canadensis var. Native	3.0
Slender Wheatgrass	Elymus Trachycaulus var. An Louis	2.2
Western Wheatgrass	Pascropyrum Smithii var. Arriba	4.8
Beardless Wheatgrass	Pseudoroegneria Spicata spp. Inermis, var. Bromar	4.5
TOTAL		23.3

B. SEEDING APPLICATION: The following seeding methods shall be used for all greas which are not surfaced and as shown on the Permanent Stabilization Site Maps. Soil compaction shall be minimized for areas where permanent stabilization will be achieved through vegetative cover.

SEEDING METHOD (subsection 212.05)		ACRE
Seeding (Native) Drill, CDOT Pay Item 212-00706		0.60
	TOTAL	0.60

The Contractor shall provide the location of where seed is stored and access to stored seed locations to the Engineer. Seed stored by the Contractor for longer than 30 days will be rejected.

- C. MULCHING APPLICATION: Apply a minimum of 2 tons of certified weed free hay or 2 1/2 tons of certified weed free straw per acre and in accordance with Section 213, and mechanically crimp it into the soil in combination with an organic mulch tackifier.
 - 1. Prior to winter shutdown or the summer seeding window closure: Uncompleted slopes shall be mulched with 2 tons of mulching (weed free) per acre, mechanically crimped into the topsoil in combination with an organic mulch tackifier in accordance with subsections 208 and 213.
- D. SPECIAL REQUIREMENTS:

Soil amendments, seedbed preparation, and permanent stabilization mulching shall be accomplished

Print Date: 3/29/22		Sheet Revisions		
File Name: I70-SH79_SWMP.	DWG	Date: Comments		
Horiz. Scale: 0.5:1	Vert. Scale: As Noted			
Unit Information	Unit Leader Initials			
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966			
2000 South Colorado Boulevard	Fax (720) 540-6801			



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

is not mulched with permanent stabilization mulch within four working days, the Contractor shall complete interim stabilization methods in accordance with subsection 208.04(e) at no additional cost to the Department. 2. Permanent stabilization mulching shall be accomplished within 24 hours of hydraulic application of

native seed.

The Contractor shall submit a proposed Permanent Stabilization Phasing Plan to the Engineer for approval showing how the SWMP Permanent Stabilization Plans will be implemented to minimize damage to seeded areas.

E. SOIL AMENDMENT REQUIREMENTS: Minimum amendment material requirements for all disturbances to receive seeding (native).

0.60 Total Acres of Seeding (Native) Drill

Orill 706	Pay Item	Description	Amount/Acre	Units	Total For This Method
ve)I	212-00700	Organic Fertilizer High N	300	Pounds	180
Seeding (Native)Drill Pay Item 212-00706	212-00701	Compost (Mechanically Applied)	65	CY	39
ing	212-00703	Humate	200	Pounds	120
eed a	212-00704	Mycorrhizae	8	Pounds	5
S T	212-00705	Elemental Sulfur	100	Pounds	60

F. SOIL RETENTION COVERING: On slopes and ditches requiring a blanket or turf reinforcement mat (trm), the blanket/trm shall be placed in lieu of mulch and mulch tackifier and placed after seeding (native). See SWMP Site Map for blanket/trm locations.

G. Permanent Stabilization Application Under Structures: Under structures shade patterns should be considered and the use of Median Cover Material (Stone) or other stabilized options with an approved Project Special Provision should be used. See SWMP Site Map for locations.

H. RESEEDING OPERATIONS/CORRECTIVE STABILIZATION:

Prior to partial acceptance.

- 1. All seeded areas shall be reviewed by the SWMP Administrator for Construction and or Engineer for bare soils caused by surface or wind erosion. Bare areas caused by surface or gully erosion, blown away mulch, etc. shall be re-graded, seeded, and have the designated mulching applied as necessary, at no additional cost to the project.
- 2. The Contractor shall maintain seeding/mulch/tackifier/blanket/TRM, mow to control weeds or apply herbicide to control weeds in the seeded areas until Partial Acceptance of the stormwater construction work.

7. PRIOR TO PROJECT FINAL ACCEPTANCE

- A. When directed by the Engineer, removal and disposal of temporary control measures shall be included in the cost of work.
- B. At the end of the project, all ditch checks shall consist of either temporary erosion logs (or equivalent) or permanent riprap.
- C. All storm drains shall be cleaned prior to the Final Acceptance of the project. If required, include work in 202-04002 Clean Culvert.
- D. Refer to Specification 208.10 for Items to be completed prior to requesting partial acceptance of water quality work

As Constructed	STORMWATER MA	Project No./Code			
No Revisions:	STORMWATER MA	STU 0704-248			
Revised:	Designer: A. MARQUEZ Structure		23180		
	Detailer: M. WAGNER	Numbers			
Void:	Sheet Subset: SWMP	Subset Sheets: 2 of 6	Sheet Number 33		

8. NARRATIVES:

Control Measure Matrixes During Construction:

- 1. Control measure narratives have been included for the CDOT Standard Specifications and Standard Plan M-208 and M-216 along with any non-standard control measures approved during the design process. If a Non-Standard Control Measure not included in the SWMP is proposed and approved by the Engineer the SWMP Administrator for Construction shall do the following: Place an "X" in the column for non-standard and complete a Non-Standard Control Measure Specification and Narrative covering the what, when, where and why the control measure is being used shall be add to the SWMP. The appropriate "X" shall also be added to the implementation phase(s).
- 2. The SWMP Administrator for Construction shall place an "X" in the column In Use On Site when the control measure has been installed.
- 3. A "B" in the Initial Activities Column indicates that the control measure shall be installed **before** construction activity starts. Locations and quantities will be discussed during the Environmental Pre-Construction Conference with the Regional Water Pollution Control Manager.

STRUCTURAL Control Measures that may be potentially used on the project for erosion and sediment control; practices may include, but are not limited to:

		*	A:	CONTROL MEASURE IMPLEMENTATION PHASE			
APPLICATION, CONTROL MEASURE	NARRATIVE		ARD USE ON SITE	INITIAL ACTIVITIES	INTERIM ACTIVITIES	PERMANENT STABILIZATION	
PROTECTION OF EXISTING WETLANDS Fence (plastic) and erosion logs	Fence (plastic) shall be placed in combination with erosion logs to prevent encroachment of construction traffic and sediment into state waters prior to start of construction disturbances. Fence (plastic) shall be placed adjacent to the wetlands; erosion logs shall be placed between the plastic fence and disturbance area. Logs shall be placed to direct flows away from or filter water running into wetlands from disturbance areas.						
PROTECTION OF EXISTING TREES/LANDSCAPING Fence (plastic)	Fence (plastic) shall be used in areas indicated in the plans to prevent encroachment of construction traffic and sediment for the protection of mature trees and/or existing landscaping prior to start of construction disturbances.						
CHECK DAM/DITCH CHECK Erosion log, silt berm, silt dike, rock check dam	Placed in ditches immediately upon completion of ditch grading to reduce velocity of runoff in ditch. For existing ditches, place prior to start of construction disturbances.	M-208					
Storm Drain Inlet Protection In Paved Roadways (Type 1, 2 and 3 as shown on M-208-1, sheet 5 of 11)	Manufactured storm drain inlet protection placed prior to construction disturbances as detailed in M-208-1, to protect existing inlets or immediately upon completion of new inlets to prevent sediment from entering the inlet throughout construction.	M-208					
Storm Drain Inlet Protection In Native Seed Areas (M-604 Standard Inlets Type C and D)	Erosion logs or aggregate bags placed around inlet grate to prevent sediment from entering inlet. Place prior to construction disturbances to protect existing inlets or immediately upon completion of new inlets.	M-208					
CULVERT INLET/OUTLET PROTECTION Erosion logs, aggregate bags	Placed at mouth of culvert inlets and over top of culvert at inlet and outlet where disturbance may be occurring adjacent to pipe to prevent sediment laden water from entering pipe or drainage. Place prior to start of construction disturbances.	M-208		х	x		
TYPE C, TYPE D AND TYPE 13 PROTECTION Erosion logs, aggregate bags, erosion bales	Placed around inlet grate or slope and ditch paving to prevent sediment from entering inlet. Place prior to start of construction disturbances.	M-208		В	x		
STOCKPILE PROTECTION Temporary berm, erosion logs, aggregate bags*	Placed within specified distance, in accordance with subsection 208.06, from toe to contain sediment around stockpile. *Aggregate bags are easily moved and replaced for access during the work day. Place prior to start of stockpile, increase control as stockpile increases size.	M-208					
TOE OF FILL PROTECTION Erosion logs, temporary berm, silt fence, topsoil windrow*	Place prior to slope/embankment work to capture sediment and protect and delineate undisturbed areas. *Can be used to stockpile topsoil for salvage.	M-208		х	x		
PERIMETER CONTROL Erosion logs, silt fence, temporary berm, topsoil windrow*	Placed prior to construction commencing to address potential run-on water from off site, and to divert around disturbed area. *Can be used to stockpile topsoil for salvage.	M-208		В	x		
SEDIMENT CONTROL/ SLOPE CONTROL Silt fence, erosion logs	Placed on the contour of a slope to contain and slow down construction runoff. Place prior to start of construction disturbances.	M-208		x	x		
TEMPORARY SEDIMENT TRAP	Used to capture sediment laden runoff from disturbed areas < 5 acres during construction. Place prior to start of construction disturbances. Outlets that withdraw water from or near the surface may be installed when discharging from basins and impoundments.	M-208					
EMBANKMENT PROTECTION OR TEMPORARY SLOPE DRAIN	Placed as a conduit or chute to drain runoff down slope and to prevent erosion of slope.	M-208					
OUTLET PROTECTION Riprap, or approved other	Material placed as energy dissipater to prevent erosion at outlet structure.	M-601-12					

Template Revised: 2/x/2021

Print Date: 3/29/22		Sheet Revisions			
File Name: I70-SH79_SWMP.DWG		Date:	Comments	Init.	
Horiz. Scale: 0.5:1	Vert. Scale: As Noted				
Unit Information	Unit Leader Initials				
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000	Tele. (720) 540-6800 (800) 490-4966				
2000 South Colorado Boulevard	Fax (720) 540-6801				




As Constructed	STODMWATED M.	TORMWATER MANAGEMENT PLAN Project No./C			
No Revisions:	STORMWATER MI	STU 0704-248			
Revised:	Designer: A. MARQUEZ Structure Detailer: M. WACNER Numbers		23180		
Void:	Detailer: M. WAGNER Sheet Subset: SWMP	Subset Sheets: 3 of 6	Sheet Number 34		

CONCRETE WASHOUT In-ground or fabricated	Construction control, used for waste management of concrete and concrete equipment cleaning. Place prior to start of concrete activities.	M-208	x	х	
VEHICLE TRACKING PAD	Source control, placed to prevent tracking of sediment from disturbed area to offsite surface. Place prior to start of construction disturbances.	M-208	В	x	
Engineered SEDIMENT BASIN	Constructed early in project, prior to storm sewer/ditches and in accordance with 208.05(p) to capture storm flow. Outlet structure and/or outfall shall be modified for temporary sediment control using an approved non-standard detail. Outlets that withdraw water from or near the surface shall be installed when discharging from basins and impoundments, unless infeasible				
DEWATERING (Contractor is responsible for obtaining a permit from Colorado Department of Health and Environment.)	Shall be done in such a manner to prevent potential pollutants from entering state waters.				
TEMPORARY STREAM CROSSING	Constructed over stream or drainage to prevent discharge of pollutants from construction equipment into water.				
CLEAN WATER DIVERSION	Placed to divert clean surface or ground water around disturbance area to prevent it from mixing with construction runoff.				
OTHER					

NON-STRUCTURAL Control Measures that may be potentially used on the project for erosion and sediment control; practices may include, but are not limited to: Erosion control devices are used to limit the amount of soil loss on site. Sediment control devices are designed to capture sediment on the project site.

				CONTROL MEASURE IMPLEMENTATION PHASE			
APPLICATION, CONTROL MEASURE	NARRATIVE	M- STANDARD or "For NON- STANDARD	IN USE ON SITE	INITIAL ACTIVITY	INTERIM ACTIVITIES	PERMANENT STABILIZATION	
VEGETATIVE BUFFER STRIP	Finishing component for filtering sediment-laden runoff from disturbance area. Area within CDOT ROW						
Fence (plastic)	or temporary easement to be identified on SWMP prior to construction starting.						
GRADING APPLICATIONS (LANDFORM)	Existing or created landforms may be used as a control measure if they prevent sediment from entering or leaving the disturbance area. If a landform directs flow of water to a concentrated outfall point, the outfall point shall be protected to prevent erosion. Area to be identified on SWMP prior to construction starting.	M-208					
TOPSOIL MANAGEMENT STOCKPILE/SALVAGE Windrow or stockpile				x	x	x	
SURFACE ROUGHENING / GRADING TECHNIQUES	Temporary stabilization of disturbance and to minimize wind and erosion.				Х		
SEEDING (TEMPORARY)	Temporary stabilization used for over wintering of disturbance or used to control erosion for areas scheduled for future construction.						
BONDED FIBER MATRIX or MULCHING (HYDRAULIC)	Not to be used in areas of concentrated flows, i.e. ditch lines. To be for either Interim or Permanent Stabilization placed as a surface cover for erosion control. May be used as surface cover when work is temporarily halted and as approved by the Engineer for stockpiles.						
Straw or Hay MULCH/MULCH TACKIFIER	Interim or Permanent Stabilization placed as a surface cover for erosion control and or seeding establishment. To be installed as Interim Stabilization as a surface cover when work is temporarily halted and as approved by the Engineer				x	х	
SPRAY-ON MULCH BLANKET (Not to be used in areas of concentrated flows, i.e. ditch lines.)	Interim or Permanent Stabilization placed as a surface cover for erosion control and or seeding establishment. To be installed as temporary surface cover when work is temporarily halted and as approved by the Engineer						
SEEDING PERMANENT (NATIVE)	Permanent Stabilization of disturbance and to reduce runoff and control erosion on disturbed areas.				x	х	
SOIL RETENTION BLANKET (SRB)	Permanent Stabilization of disturbance and to reduce runoff and control erosion on disturbed areas.	M-216			х	х	

	Print Date: 3/29/22		
	File Name: I70-SH79_SWMP.D	WG	
	Horiz. Scale: 0.5:1	Vert. Scale: As Noted	
ſ	Unit Information	Unit Leader Initials	
	Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000 2000 South Colorado Boulevard Denver, CO 80222-7900	Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801	(





STODMINATED MA	Project No./Code	
STORMWATER IMA	STU 0704-248	
		23180
		Sheet Number 35
	Designer: A. MARQUEZ	Detailer: M. WAGNER Numbers

PM kdunis
3:43
N70-SH79_SWMP.dwg 3/14/2022 3:43 PM
33
gwb.
_SWMP
H79
S-0
gg
jn\Drawir
Desic
Design∖
Interchange
Bennett
58279\
Ĕ
X:\AE\B\BENNT\158279\Ben
×

TURF REINFORCEMENT MAT (TRM)	Permanent Stabilization of disturbance and to reduce runoff and control erosion on disturbed areas. Placed in channels or on slopes for erosion control, channel liner and seeding establishment. M-216			
Sweeping	Source control, used to remove sediment tracked onto paved surfaces and to prevent sediment from entering drainage system. Sweep daily and at the end of the construction shift as needed. Kick brooms shall not be permitted.	х	x	x
OTHER				

Print Date: 3/29/22	
File Name: I70-SH79_SWMP.I	DWG
Horiz. Scale: 0.5:1	Vert. Scale: As Noted
Unit Information	Unit Leader Initials
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000 2000 South Colorado Boulevard	Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

	Sheet Revisions	
Date: Comments		Init.



	OF BE	
BENNE	ETT, CC	80102
TELE.	(303)	644-3249
FAX	(303)	644-4125
	` '	

STORMWATER MANAGEMENT DIANI			Project No./Co			ode	
STORMWATER MANAGEMENT PLAN				STU 0704-248			
		4 1				23180	
Detailer: M.	WAGNER	Numbers					
Sheet Subset: SWMP		Subset S	heets:	5 (of 6	Sheet Number	36
	Designer: A. M. Detailer: M.	Designer: A. MARQUEZ Detailer: M. WAGNER	Designer: A. MARQUEZ Structure Detailer: M. WAGNER Numbers	Designer: A. MARQUEZ Structure Detailer: M. WAGNER Numbers	Designer: A. MARQUEZ Structure Detailer: M. WAGNER Numbers	Detailer: M. WAGNER Numbers	Designer: A. MARQUEZ Structure 23180 Detailer: M. WAGNER Numbers

E\B\BENNT\158279\Bennett Interchange Design\Design\Drawings\170-SH79_SWMP.dwg 3/14/2022 3:43 PM kdu

9. TABULATION OF STORMWATER QUANTITIES

A. Control Measure sediment removal and disposal shall be paid for as: 208 Removal and Disposal of Sediment (Equipment) and 208 Removal and Disposal of Sediment (Labor). All other control measure maintenance shall be included in the cost of the control measure.

PSP Spec.	Pay Item	Description	Pay Unit	Initial Const	Interim Const.	Permanent Stabilization	*Total Quantity
Χ	202-04002	Clean Culvert	Each	4		1	5
	207-00700	Topsoil (Onsite)	CY			485	485
	207-00704	Subgrade Soil Preparation	SY			2909	2909
	208-00002	Erosion Log Type 1 (12 inch)	LF	150	150		300
	208-00020	Silt Fence	LF	1800			1800
	208-00046	Pre-fabricated Concrete Washout Structure (Type 1)	Each		1		1
	208-00075	Pre-fabricated Vehicle Tracking Pad	Each	2			2
	208-00103	Removal and Disposal of Sediment (Labor)	Hour		8		8
	208-00105	Removal and Disposal of Sediment (Equipment)	Hour		8		8
	208-00106	Sweeping (Sediment Removal)	Hour	8	8	8	24
	212-00706	Seeding (Native) Drill	Acre		0.90	0.60	1.50
	213-00002	Mulching (Weed Free Hay)	Acre		0.48	0.32	0.80
	213-00061	Mulch Tackifier	LB		97	65	162
	216-00201	Soil Retention Blanket (Straw/Coconut) (Biodegradable class 1)	SY		2019	1346	3365
	217-00020	Herbicide Treatment	Hour			8	8
X	700-70380	F/A Erosion Control	FA	0.33	0.33	0.33	1

*It is anticipated that additional control measures and control measure quantities not shown on the SWMP Site Maps shall be required on the project for unforeseen conditions and replacement of items that are beyond their useful service life, see subsections 208.03 and 208.04. Quantities for all control measures shown above are estimated, and have been increased for unforeseen conditions and normal control measure life expectancy. Quantities shall be adjusted according to the conditions encountered in the field as directed and approved by the Engineer. Payment shall be for the actual work completed and material used.

Pay Item 208-00071 is included for anticipated maintenance of vehicle tracking pads based on the service life of the control measure in the field. The use of the material shall be directed and approved by the Engineer. *** Using Erosion Control Management Pay Item on the project must be approved by the Regional Environmental Staff and Engineer. See 208.11 for method of measurement for the day pay unit. * F/A refers to CDOT's Force Account Pay Items.

10. BIOLOGICAL IMPACTS and DEWATERING

- A. ENVIRONMENTAL IMPACTS:
 - 1. Wetland Impacts: NO
 - 2. Stream Impacts: NO
 - 3. Threatened and Endangered Species: No species are anticipated to be impacted by the project.
- Print Date: 3/29/22

 File Name: I70-SH79_SWMP.DWG

 Horiz. Scale: 0.5:1 Vert. Scale: As Noted

 Unit Information Unit Leader Initials

 Short Elliott Hendrickson Inc.
 Colorado Center Tower One
 Suite 6000
 Suite 6000
 Suite 6000
 Suite 6000
 South Colorado Boulevard

 Short Elliott Hendrickson Inc.
 Fax (720) 540-6800
 Suite 6000
 South Colorado Boulevard

 Fax (720) 540-6800
 Suite 6000
 South Colorado Boulevard



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

Project No./Code As Constructed STORMWATER MANAGEMENT PLAN No Revisions: STU 0704-248 A. MARQUEZ Structure Designer: Revised: 23180 M. WAGNER Numbers 37 Void: Sheet Number SWMP Subset Sheets: 6 of 6 Sheet Subset:


A. <u>DEWATERING</u>: (Not covered under the CDPHE guidance document Low Risk Discharge Guidance Discharges of Uncontaminated Groundwater to Land): https://www.colorado.gov/pacific/sites/default/files/WQ%20LOW%20RISK%20GW.pdf

1. Dewatering: Refer to other environmental permits in accordance with subsection 107.02 and the permits contained in Tab 16 of the SWMP.

2. If groundwater does not meet water quality standards for receiving water a separate CDPS Dewatering Permit shall be obtained by the Contractor from CDPHE in accordance with subsections 107.02 and 107.25.

11. NOTES

- 1. EMC (or SWMP Administrator for Construction or Erosion Control Inspector) is included in the cost of the work.
- 2. Wetlands were not delineated with this project. Contractor shall protect all wetlands within the project area if needed.
- 3. Items required for miscellaneous erosion control work as directed by the Engineer will not be measured and paid for separately, but shall be included in the cost of the work.



X:AE\B\BENNT\158279\Bennett Interchange Design\Drewings\170-SH79 Erosion Control Plan.dwg 3/1/2022 4:58 PM kclu

UTILITY GENERAL NOTES

- 1. UTILITIES AS SHOWN ON THE PLAN SHEETS ARE PLOTTED FROM THE BEST AVAILABLE INFORMATION. THE CONTRACTOR'S ATTENTION IS DIRECTED TO SUBSECTION 105.11 OF THE STANDARD SPECIFICATIONS CONCERNING UTILITIES.
- 2. UTILITIES ARE DEPICTED ON THESE PLANS IN ACCORDANCE WITH THEIR ACHIEVED QUALITY LEVEL AS DEFINED IN THE AMERICAN SOCIETY OF CIVIL ENGINEER'S DOCUMENT ASCE 38 "STANDARD GUIDELINE FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA." RELIANCE UPON THIS DATA FOR RISK MANAGEMENT PURPOSES DURING BIDDING DOES NOT RELIEVE THE EXCAVATOR OR UTILITY OWNER FROM FOLLOWING ALL APPLICABLE UTILITY DAMAGE PREVENTION STATUTES, POLICIES, AND/OR PROCEDURES DURING CONSTRUCTION.
- 3. THE CONTRACTOR SHALL COMPLY WITH ARTICLE 1.5 OF TITLE 9, CRS ("EXCAVATION REQUIREMENTS") WHEN EXCAVATING OR GRADING IS PLANNED IN THE AREA OF UNDERGROUND UTILITY FACILITIES. THE CONTRACTOR SHALL NOTIFY ALL AFFECTED UTILITIES AT LEAST TWO (2) BUSINESS DAYS, NOT INCLUDING THE ACTUAL DAY OF NOTICE, PRIOR TO COMMENCING SUCH OPERATIONS. THE CONTRACTOR SHALL CONTACT COLORADO 811 (FORMERLY UTILITY NOTIFICATION CENTER OF COLORADO (UNCC)) AT PHONE NO. 811 OR CO811.ORG, TO HAVE LOCATIONS OF COLORADO 811 REGISTERED LINES MARKED BY MEMBER COMPANIES. ALL OTHER UNDERGROUND FACILITIES SHALL BE LOCATED BY CONTACTING THE RESPECTIVE OWNER. UTILITY SERVICE LATERALS SHALL ALSO BE LOCATED PRIOR TO BEGINNING EXCAVATION OR GRADING.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATION AND DEPTH OF ALL EXISTING UTILITIES AS NECESSARY TO ENSURE THAT THE UTILITIES WILL NOT BE IMPACTED BY CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL COORDINATE WITH THE UTILITY OWNERS TO BE ON—SITE DURING POTHOLING. IF EXISTING UTILITIES ARE WITHIN CLOSE PROXIMITY HORIZONTALLY OR VERTICALLY TO PROPOSED INSTILLATIONS, THE CONTRACTOR SHALL CONTACT THE ENGINEER. ANY EXISTING UTILITY, WHICH IS TO REMAIN BUT IS DAMAGED AS A RESULT OF THE CONTRACTOR'S OPERATION, SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE.
- 5. CDOT UTILITY AS-CONSTRUCTED REQUIREMENTS, DATA CONTENT AND ACCURACY 1.1. ALL UTILITY INSTALLATIONS, WITHIN CDOT RIGHT OF WAY (ROW), SHALL BE COLLECTED USING CDOT'S MOBILE APPLICATION (POINTMAN). IF REQUIRED PLEASE CONTACT CDOT AT CDOTPOINTMAN@GMAIL.COM IN ORDER TO OBTAIN NEW LOGIN AND PASSWORD INFORMATION. DOWNLOAD POINTMAN MOBILE APPLICATION THROUGH THE APPLE STORE (IOS) OR GOOGLEPLAY (ANDROID). FINALLY, PLEASE WATCH THE FOLLOWING QUICK START GUIDE, THE VIDEO CAN BE FOUND AT THE FOLLOWING LINK: HTTPS://YOUTU.BE/X-TMVNK7VZW

UTILITY CONTACT LIST

UTILITY OWNER	UTILITY	CONTACT PERSON(S)	PHONE NUMBER	EMAIL
ALTERNATIVE ENERGY SOLUTIONS	FIBER	MARK RAY	303-947-4641	1.CLR.INC@GMAIL.COM
BIJOU TELEPHONE COOP	FIBER / PHONE	BRIAN CREVELING	303-822-5400	CREVELING@NETECIN.NET
CENTURY LINK (LUMEN)	FIBER	THOMAS LONGAN		THOMAS.LONGAN@CENTURYLINK.COM
EASTERN SLOPE RURAL TELEPHONE	FIBER/PHONE	CLINT FELZIEN	719-743-2460	CLINTF@ESTRA.COM
CORE (INTERMOUNTAIN REA)	ELECTRIC	GIS DEPARTMENT		MAPS@IREA.COOP
CDOT REGION 1	ELECTRIC, FIBER, FIBER BACKBONE	JILL SCOTT	303-512-5805	JILL.SCOTT@STATE.CO.US
ZAYO BANDWITH	FIBER	ERIC BOE	303-481-6121	ERIC.BOE@ZAYO.COM

l .	
Print Date: 3/29/22	
File Name: I70-SH79_UTILITY	PLAN.DWG
Horiz. Scale: 0.5:1	Vert. Scale: As Noted
Unit Information	Unit Leader Initials
Short Elliott Hendrickson Inc. Colorado Center Tower One Suite 6000 2000 South Colorado Boulevard	Tele. (720) 540-6800 (800) 490-4966 Fax (720) 540-6801

Sheet Revisions					
Date:	Comments	Init.			



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644–3249 FAX (303) 644–4125

	As Constructed		UTILITY	NOTEC		Project No./Co	ode	
	No Revisions:		UTILITI	NOIES			STU 0704-248	
	Revised:	Designer:	A. MARQUEZ	Structure			23180	
ŀ		Detailer:	K. KULESZA	Numbers				
	Void:	Sheet Subs	set: UTILITY	Subset S	heets: 1	of 2	Sheet Number	41

X:\AE\B\BENN\T\158279\Bennett Interchange Design\Drawings\\T0-SH79 Utility Plan.dwg 3/1/2022 2:17 PM kclunis

I-70 (EXIT 304)/SH-79 Interchange Improvements SUE Utility Investigation - Phase 1 and Phase 2

BENNETT, CO



PROJECT LOCATION MAP

800	800	400		
	Fe			

SHEET NO. **INDEX OF SHEETS**

- TITLE SHEET
- GENERAL NOTES AND MAP KEY
- PLAN UTILITY DRAWING

PROJECT AREA



Print Date: 1/5/22			Sheet Revisions	
File Name: I-70_and_SH-79_Exutil.dwg		Date:	Comments	Init.
Horiz. Scale: 1" = 200' Vert. Scale: As N	oted	2/26/21	ORIGINAL	ABRH
Unit Information Unit Leader Initials		5/3/21	REV 1	ABRH
UTILITY MAPPING SERVICES 15065 W. 44th Ave. Golden, CO 80403		1/5/22	PHASE 2	ABRH
Golden, CO 80403 (720)230-0780		2/25/22	UPDATE CORE OWNERSHIP	ABRH



No Revisions:	I—70 (EXIT 3 INTERCHANGE I EXISTING	Project No./Code	
Revised:	Designer: ABRH	Structure	
	Detailer: ABRH	Numbers	
Void:	Sheet Subset: UTIL	Subset Sheets: 1 of 3	Sheet Number 01

Survey Information:

This plan set shows subsurface and aerial utilities for the Phase 1 field investigation as of January/February 2021, and the Phase 2 investigation as of December 2021 and are subject to change. The engineering survey of the surface features and field delineated buried utilities was completed by UMS, Inc personnel. City and County of Denver approved survey control was used to tie all survey data to the project coordinate system. Control points CP104, CP107, and CP108 were used for site calibrations. The transcription of survey data to the CADD plans was completed by UMS, Inc.

Subsurface Utility Engineering (SUE) Notes:

For this project, UMS Inc. was responsible for the field designating of the existing buried utilities to the extent practical and as detailed in the authorized scope of work for this project. Users of this data set must understand and adhere to the limitations associated with the designated Quality Levels assigned to the depicted facilities. UMS, Inc. recommends that vacuum excavations or other nondestructive methods are used to obtain 3D data on utilities in potential conflict with proposed design and construction. UMS, Inc. strongly recommends users of this data become orientated with the ASCE/CI 38-02 standard guidelines and the corresponding data limitations inferred by the designated Quality Levels prior to employing the data set for design purposes. In addition, the SUE report(s) for this project must always accompany the existing utility reference CADD file to ensure proper interpretation and usage of the data set.

SUE Quality Levels:

SUE Phase I (Designating) and Phase II (Locating) activities enable the assignment of ASCE/CI 38-02 "Quality Levels" to the depicted underground utilities. The following four Quality Levels are used to identify the degree of reliability to which the utilities are depicted:

- Quality Level (QL) D: Information derived from existing records and/or oral recollections. This information is adequate for rudimentary planning or background purposes only.
- QL C: Information obtained by surveying and plotting visible above ground utility features and by using professional judgment in correlating this information to QL D data. Use of this information alone may result in 15 30% of underground utilities omitted or mapped with more than two feet of error, according to FHWA studies.
- QL B: Information obtained through the application of appropriate surface geophysical methods to determine the existence and approximate horizontal position of subsurface utilities. QL B observations should be reproducible by surface geophysics at any point along the corresponding depiction. This information is tied to the project survey control points to tolerances defined by the work scope and reduced onto plan documents.
- QL A: These observations provide discrete and precise horizontal and vertical coordinates by the actual exposure subsequent measurement of the subsurface utility at a specific point. Vacuum excavation equipment is typically used to minimize the potential for utility damage.

Note — Although reproducible, QL B positions can be influenced by physical factors that distort geophysical observations and the resulting interpreted location. For example, with inductive electromagnetic methods, adjacent conductors may create secondary magnetic fields that superposition with the primary field, causing the resulting apparent position to be slightly different from the actual position.

Disclaimer

A possibility exists that abandoned, forgotten, non-detectable, undocumented or newly installed utilities may be overlooked using standard Investigative procedures. This information is for design purposes only; markings placed on the ground or depictions developed by UMS are not intended to be used in lieu of Call 811 for excavation purposes. The use of this information by others does not relieve a contractor from the duty to comply with applicable utility prevention damage laws and regulations, including but not limited to, giving notifications to utility owners or "One Call / Call Before You Dig (811)" prior to excavation.

Refer to ASCE/CI 38-02 Standard Guideline for the Collection and Depiction of Existing Subsurface Utility Data and the ASCE Subsurface Utility Engineering for Municipalities for more information.

- * All UMS survey information obtained during the SUE investigation is based on an Engineering Survey.
- ** Unless otherwise noted, all aerial installation depictions are based on surveyed pole locations and apparent cable/conductor connectivity as observed and logged by UMS field crews.

Aerial background Imagery is for general reference only.

Print Date: 1/5/22				Sheet Revisions	
File Name: I—70_and_SH—79_Exutil.dwg			Date:	Comments	Init.
Horiz. Scale:	Vert. Scale: As Noted		2/26/21	ORIGINAL	ABRH
Unit Information Unit Leader Initials			5/3/21	REV 1	ABRH
UTILITY MAPPING SERVICES 15065 W. 44th Ave. Golden, CO 80403	5		1/5/22	PHASE 2	ABRH
Golden, CO 80403 (720)230-0780			2/25/22	UPDATE CORE OWNERSHIP	ABRH



UTILITY MAPPING/RECORDS CONTACT LIST

Utility	Utility Type	Contact	Phone/Email
Alternative Energy Solutions	Fiber	Mark Ray	303-947-4641, 1.clr.inc@gmail.com
Bijou Telephone Co-op Association	Fiber, Telephone	Brian Creveling	303-822-5400, creveling@netecin.net
CenturyLink (Lumen)	Fiber		1-877-366-8344, relocations@centurylink.com
CDOT Region 1	Electric, Fiber, Fiber Backbone	Jill Scott	303-512-5805, jill.scott@state.co.us
Eastern Slope Rural Telephone Association	Fiber, Telephone	Clint Felzien	719-743-2460, clintf@estra.com
CORE Electric Cooperative	Electric		1-800-332-9540
Zayo Bandwidth	Fiber	Robert Williams	303-632-0017, robertd.williams@zayo.com

LEGEND

F0F0F0F0	EXISTING BURIED FIBER LINE
	EXISTING BURIED NATURAL GAS LINE
εεεε	EXISTING BURIED POWER LINE
	EXISTING BURIED SANITARY SEWER LINE
	EXISTING BURIED STORM SEWER LINE
TV TV TV TV	EXISTING BURIED TELEPHONE LINE
www	EXISTING BURIED WATER LINE
	PROJECT BOUNDARY

EQUIPMENT USED

Radiodetection RD8000 Cable Locator

Trimble TSC7 Data Collector

Trimble R10 GNSS System

FIBER MANHOLE

GAS VALVE

GUY ANCHOR

TELEPHONE PED

POWER POLE

SANITARY SEWER MANHOLE

STORM DRAIN CULVERT

☐ STORM DRAIN INLET

STORM DRAIN MANHOLE


→ WATER FIRE HYDRANT

W WATER MANHOLE

WATER METER


■ WATER VALVE


♦ TEST HOLE




XSECT

Subset Sheets: 1 of 4







Print Date: 3/29/22	
File Name: I70—SH79_CROSS	SECTIONS.DWG
Horiz. Scale: 0.5:1	Vert. Scale: As Noted
Unit Information	Unit Leader Initials
Short Elliott Hendrickson Inc. Colorado Center Tower One	Tele. (720) 540-6800

Sheet Revisions					
Date:	Comments	Init.			



TOWN OF BENNETT 207 MUEGGE WAY BENNETT, CO 80102 TELE. (303) 644-3249 FAX (303) 644-4125

As Constructed	CROSS S	Project No./Code		
No Revisions:	I-70 EB	STU 0704-248		
Revised:	Designer: A. MARQUEZ		23180	
	Detailer: K. KULESZA	Numbers		
Void:	Sheet Subset: XSECT	Subset Sheets: 3 of 4	Sheet Number XS3	